


energyLogic
analysis. insight. answers.

toll free: 800.315.0459
www.nrglogic.com




ENERGY STAR REV 7 OVERVIEW WITH DETAIL EMPHASIS ON THE HVAC CONTRACTOR & RATER CHECKLIST

Presented by: Robby Schwarz


The Power of ENERGY STAR

- 80% brand recognition
- 92% influence on purchasing


> 4,500 builders



1.3 million homes
> 30% of 2011 new homes



Year	Millions of Certified Homes
2001	0.05
2002	0.1
2003	0.2
2004	0.35
2005	0.5
2006	0.7
2007	0.85
2008	0.95
2009	1.05
2010	1.15
2011	1.3



Market Realities




WASHINGTON

- The U.S. Environmental Protection Agency (EPA) announced that of all single-family homes built nationally
 - 21% in 2009
 - 25% in 2010
 - 26% in 2011

- Colorado Market share of ESNHs
 - 2004 - 4.2%
 - 2009 - 28%
 - 2010 - 45%
 - 2011 - 43%
 - 2012 - Going down?
 - 2013 going back up

What's in ENERGY STAR?



Use the correct checklist



- ENERGY STAR Qualified Homes
- ENERGY STAR Qualified Homes, Version 3 (Rev. 01)
- ENERGY STAR Qualified Homes, Version 3 (Rev. 02)
- ENERGY STAR Qualified Homes, Version 3 (Rev. 03)
- ENERGY STAR Qualified Homes, Version 3 (Rev. 04)
- ENERGY STAR Qualified Homes, Version 3 (Rev. 05)
- ENERGY STAR Qualified Homes, Version 3 (Rev. 06)
- ENERGY STAR Certified Homes, Version 3 (Rev. 07)
- National Program Requirements


Certifying Homes

The following homes are eligible to earn the ENERGY STAR:

- Detached dwelling units¹ (e.g. single family homes); OR
- Dwelling units¹ in any multifamily building with 4 units or fewer; OR
- Dwelling units¹ in multifamily buildings with 3 stories or fewer above-grade^{2,3}; OR
- Dwelling units¹ in multifamily buildings with 4 or 5 stories above-grade^{2,3} that have their own heating, cooling, and hot water

Rev 7 Thermal Enclosure Checklist


- ESv3 - Knee wall air barrier
 - Missing attic side air barrier
 - R-21 in all direction



EnergyLogic's knee wall requirement


- Knee walls 6" or Less

The installed depth of the insulation must be equal to or greater than the height of the kneewall in order to forego kneewall backing. The installed insulation angle should not exceed 45 degrees to ensure that the mounded insulation provides a minimum acceptable insulation depth over the corner of such structures and to ensure that it will not slide off. The depth of the insulation as illustrated by the two red arrows shall be equal hence ensuring at least and R-38 over the outside edge of the kneewall.



- Knee wall greater than 6"

For short knee walls and for raised ceilings that are higher than 6" and or the ceiling below, the best practice is to install a full attic side air barrier and six sided enclosed cavity insulation. The air barrier should extend above the raised ceiling, to act as an insulation dam, to ensure that the higher insulation does not fall off the top plate onto the insulation below.



Small Knee Wall Done Right



Insulated Headers: R-5: Intent vs. Exception

Exception – Where framing plan indicates that full depth solid headers are used




Insulation over the Top Plate:

Baffle and Minimum R-21 in CZ-5



Framing limited at all windows and doors



- Framing at windows shall be limited to a maximum
 - One pair of king studs per window opening
 - One pair jack studs per window opening to support the header and window sill
 - Additional jack studs shall be used only as needed for structural support
 - Cripple studs only as needed to maintain on-center spacing of studs



Footnote #21 [\(Exception\)](#)

- **“In Climate Zones 5 - 8, a minimum stud spacing of 16 in. o.c. is permitted to be used with 2x6 framing if \geq R-20.0 wall insulation is installed”**
- Regardless, all vertical framing members shall either be on-center or have an alternative structural purpose (e.g., framing members at the edge of pre-fabricated panels) that is apparent to the Rater or documented in a framing plan...
- The Rater need not evaluate the structural necessity of the framing plan to qualify the home.
- However, all 2x6 framing with stud spacing of 16 in. o.c. in Climate Zones 5 - 8 shall have \geq R-20.0 wall insulation installed regardless of any framing plan or alternative equivalent total UA calculation.”



HVAC Contractors Checklist



HVAC System Quality Installation Rater Checklist - page one

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist¹

Home Address	City	State	Zip Code	Must Correct	Rate Verified	N/A
1. Review of HVAC System Quality Installation Contractor Checklist¹						
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation systems (1.3), full load calculations (2.19), and AHRI certificates (3.13).						
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist Item # indicated in parentheses):						
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location ¹						
1.2.2 Home orientation (2.3) matches orientation of rated home						
1.2.3 Number of occupants (2.6) equals number of occupants in rated home ¹						
1.2.4 Conditioned floor area (2.7) is within ±10% of conditioned floor area of rated home						
1.2.5 Window area (2.8) is within ±10% of calculated window area of rated home						
1.2.6 Predominant window SHGC (2.8) is within 0.1 of predominant value in rated home ¹						
1.2.7 Listed latent cooling capacity (3.8) exceeds design latent heat gain (2.12)						
1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13)						
1.2.9 Listed total cooling capacity (3.10) is 95-115% (or 95-120% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size						
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 5.1), and AHRI certificates or OEM catalog data all match						
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (as determined using pressure-temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees)						
1.2.12 Calculated subcooling (7.1 minus 4.4) value is within ±3°F of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within ±5°F of the reported target temperature (7.7)						
1.3 Rater-verified supply & return duct static pressure ≤ 110% of contractor values (9.3, 9.4)						
1.4 Contractor prepared balancing report including the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflows measured and documented on balancing report through one of the following options:						
1.4.1 Measured and documented by contractor (10.1.1), OR:						
1.4.2 Measured by Rater using Section 804.2 of the Mortgage Industry National IERS Standard, documented by Rater. As verified by Rater, the system static pressure is within the greater of a 20% or 25 cFM of design airflow (10.1.2)						
1.5 HVAC contractor holds credentials necessary to complete the HVAC System QI Contractor Checklist ¹¹						
2. Duct Quality Installation - Applies to All Heating, Cooling, Ventilation, Exhaust, and Pressure Balancing Ducts¹²						
2.1 Connections and routing of ductwork completed without kinks or sharp bends.						
2.2 No excessive coiled or looped flexible ductwork.						
2.3 Flexible ducts in unconditioned space installed in cavities smaller than outer duct diameter; in conditioned space not installed in cavities smaller than inner duct diameter						
2.4 Flexible ducts supported at intervals as recommended by mfr, but at a distance ≤ 5 ft.						
2.5 Building cavities not used as supply or return ducts unless they meet items 3.2, 3.3, 4.1, and 4.2 of this Checklist.						
2.6 HVAC ducts, cavities used as ducts, and combustion airtight and outlets may pass perpendicularly through exterior walls, but shall not be run within exterior walls unless at least R-5 continuous insulation is provided on exterior side of the cavity, along with an interior and exterior air barrier where required by the Thermal Enclosure System Rater Checklist.						
2.7 Quantity & location of supply and return duct terminals match contractor balancing report. ¹³						
2.8 Bedrooms pressure-balanced using any combination of transfer grills, jump ducts, dedicated return ducts, and/or unvented doors to either: a) provide 1 sq. in. of free area opening per 1 CFM of supply air, as reported on the contractor-provided balancing report; or b) achieve a Rater-measured pressure differential ≤ 3 Pa with respect to the main body of the house when all bedroom doors are closed and all handiers are operating.						
3. Duct Insulation - Applies to All Heating, Cooling, Supply Ventilation, and Pressure Balancing Ducts¹⁴						
3.1 All connections to trunk ducts in unconditioned space are insulated.						
3.2 Prescriptive Path: Supply ducts in unconditioned attics have insulation ≥ R-6, Performance Path: Supply ducts in unconditioned attics have insulation ≥ R-6.						
3.3 All other supply ducts and all return ducts in unconditioned space have insulation ≥ R-6.						

- Collect and Review
 - HVAC Contractor Checklist
 - Ventilation System Design
 - Full Load calculations
 - AHRI Certificates
 - Balancing report

HVAC System Contractor Checklist Section

Footnote #1

Footnote: #1

- This Checklist is designed to :
 - ASHRAE 62.2-2010 and ANSI / ACCA's 5 QI2007 protocol
 - Improving the performance of HVAC equipment in new homes when compared to homes built to minimum code
- However, these features alone cannot prevent all HVAC problems (e.g., those caused by a lack of maintenance by occupants)
- Therefore, this Checklist is **not a guarantee** of proper ventilation, indoor air quality, or HVAC performance
- This Checklist applies to:
 - Ventilation systems
 - Split air conditioners
 - Unitary air conditioners,
 - Air-source / water-source (i.e., geothermal) heat pumps up to 65,000 Btu / h and furnaces up to 225,000 Btu / h
- All other equipment, including boilers, are exempt
- If the ventilation system is the only applicable system installed in the home, then only Section 1 shall be completed
- One Checklist shall be completed for each system and provided to the Rater.
- The Checklist **CANNOT** be used to demonstrate compliance with the Indoor airPLUS specifications

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist¹

Home Address	City	State	Zip Code	Yes	No	N/A
1. Whole Building Mechanical Ventilation Design¹						
1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in items 1.2.1.5.						
1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate automatically and automatically based on a timer and to restrict outdoor air intake when mfr use is not recommended.						
1.3 Documentation is attached with ventilation system type, location, design rate, and frequency and duration of each ventilation cycle.						
1.4 If present, continuously-operating vent & exhaust fans designed to operate during all occupant hours.						
1.5 If present, intermittently-operating whole-house ventilation system designed to substantially operate an equal amount per day and at least 75% of every 24 hours.						
2. Heating & Cooling System Design² - Parameters used in the design calculations and other items in full, specific, neither design nor construction, nor final as-installed, nor as-reported, and other parameters not shown.						
2.1 Heat Loss Due to Infiltration: <input type="checkbox"/> Manual <input type="checkbox"/> ASHRAE <input type="checkbox"/> Other						
2.2 Duct Design Method: <input type="checkbox"/> Manual <input type="checkbox"/> Other						
2.3 Equipment Selection Method: <input type="checkbox"/> Manual <input type="checkbox"/> OEM Res. <input type="checkbox"/> Other						
2.4 Outdoor Design Temperature ³ : Location: _____ °F						
2.5 Orientation of Rated Home (e.g., North, South): _____ °F						
2.6 Number of Occupants Served by System ⁴ : _____						
2.7 Conditioned Floor Area in Rated Home ⁵ : _____ Sq. Ft.						
2.8 Window Area in Rated Home: _____ Sq. Ft.						
2.9 Predominant Window SHGC in Rated Home ⁶ : _____						
2.10 Infiltration Rate in Rated Home ⁷ : Summer _____ Winter _____						
2.11 Mechanical Ventilation Rate in Rated Home: _____ CFM						
2.12 Design Latent Heat Gain: _____ BTU/h						
2.13 Design Sensible Heat Gain: _____ BTU/h						
2.14 Design Total Heat Gain: _____ BTU/h						
2.15 Design Total Heat Loss: _____ BTU/h						
2.16 Design Airflow ⁸ : _____ CFM						
2.17 Design Duct Static Pressure ⁹ : _____ in. Water Column						
2.18 Full Load Calculations Report Attached ¹⁰ : <input type="checkbox"/>						
3. Selected Cooling Equipment, If Cooling Equipment to be Installed						
3.1 Condenser Manufacturer & Model: _____						
3.2 Evaporator / Fan Manufacturer & Model: _____						
3.3 AHRI Reference # ¹¹ : _____						
3.4 Listed EER/SEER: _____						
3.5 Minimum Design Type: <input type="checkbox"/> TSV <input type="checkbox"/> Fixed orifice <input type="checkbox"/> Other						
3.6 Refrigerant Type: <input type="checkbox"/> R-410a <input type="checkbox"/> Other						
3.7 Fan Speed Type ¹² : <input type="checkbox"/> Fixed <input type="checkbox"/> Variable (ECM) / ECM <input type="checkbox"/> Other						
3.8 Listed Sys. Latent Capacity at Design Cond. ¹³ : _____ BTU/h						
3.9 Listed Sys. Sensible Capacity at Design Cond. ¹⁴ : _____ BTU/h						
3.10 Listed Sys. Total Capacity at Design Cond. ¹⁵ : _____ BTU/h						
3.11 Design Latent Heat Gain (Table 2.12, ASHRAE 62.2-2010) verified by manufacturer installed.						
3.12 Design Sensible Heat Gain (Table 3.10) is 95-110% of Design Total Heat Gain (Table 2.14) or next nominal size. ¹⁶						
3.13 AHRI Certificate Attached ¹⁷ : <input type="checkbox"/>						
4. Selected Heat Pump Equipment, If Heatpump to be Installed						
4.1 AHRI COP or Seasonal COP: _____						
4.2 Performance at 17°F: Capacity _____ BTU/h Efficiency _____ COP ¹⁸						
4.3 Performance at 47°F: Capacity _____ BTU/h Efficiency _____ COP ¹⁹						

HVAC System Contractor Checklist Section

Footnote #2

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist ¹

Home Address: _____ City: _____ State: _____

System Description ² _____ Cooling system for temporary occupant load? ³ Yes No

1. Whole-Building Mechanical Ventilation Design ¹

1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5. Yes No

1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate intermittently and automatically based on a timer and to restrict outdoor air intake. Yes No

2. Selected Cooling Equipment, if Cooling Equipment to be Installed

3.1 Condenser Manufacturer & Model: _____

3.2 Evaporator / Fan Coil Manufacturer & Model: _____

3.3 AHRI Reference #: _____

3.4 Listed Efficiency: _____ EER _____ SEER _____

3.5 Heating Coefficient of Performance (COP): _____

3.6 Refrigerant Type: R-410a R-410a Other _____

3.7 Fan Speed Type: Fixed Variable (ECM/ICM) Other _____

3.8 Listed Sys. Latent Capacity at Design Cond.: _____ BTU/h

3.9 Listed Sys. Total Capacity at Design Cond.: _____ BTU/h

3.10 Listed Sys. Latent Capacity (Value 3.8) ÷ Design Latent Heat Gain (Value 2.12), ENERGY STAR certified dehumidifier installed: Yes No

3.11 If Listed Sys. Latent Capacity (Value 3.8) ÷ Design Latent Heat Gain (Value 2.12) is 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size: Yes No

3.12 Listed Sys. Total Capacity (Value 3.10) ÷ 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size: Yes No

3.13 AHRI Certificate Attached: Yes No

4. Selected Heat Pump Equipment, if Heatpump to be Installed

4.1 AHRI Listed Efficiency: _____ HSPF or Ground Source COP _____

4.2 Performance at 17°F: Capacity _____ BTU/h Efficiency _____ COP ¹¹

4.3 Performance at 47°F: Capacity _____ BTU/h Efficiency _____ COP ¹¹

- Description of HVAC system location or area served e.g.
 - Whole house
 - Upper level
 - lower level

HVAC System Contractor Checklist Section

Footnote #3

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist ¹

Home Address: _____ City: _____ State: _____

System Description ² _____ Cooling system for temporary occupant load? ³ Yes No

1. Whole-Building Mechanical Ventilation Design ¹

1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5. Yes No

1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate intermittently and automatically based on a timer and to restrict outdoor air intake. Yes No

2. Heating & Cooling System Design ¹⁰ *Parameters used in the design calculations shall reflect home to be built, specific, outdoor design conditions, home structure, number of bedrooms, conditioned floor area, window area, predominant window performance and installed work, infiltration rate, mechanical ventilation rate, presence of HRV or ERV or other filter, and indoor temperature setpoints + 1°F for heating, 1°F for cooling*

2.1 Heat Loss (Gain) Method: Manual J Manual D Other _____

2.2 Duct Design Method: Manual S Manual D Other _____

2.3 Equipment Selection Method: Manual S OEM Rec. Other _____

2.4 Outdoor Design Temperature: ¹¹ Location _____ °F _____ °F _____ °F

2.5 Orientation of Rated Home (e.g., North, South): _____

2.6 Number of Occupants Served by System: _____

2.7 Conditioned Floor Area in Rated Home: _____ Sq. Ft.

2.8 Window Area in Rated Home: _____ Sq. Ft.

2.9 Predominant Window (SHGC) in Rated Home: ¹² Summer _____ Winter _____

2.10 Infiltration Rate in Rated Home: _____ CFM

2.11 Mechanical Ventilation Rate in Rated Home: _____ CFM

2.12 Design Latent Heat Gain: _____ BTU/h

2.13 Design Sensible Heat Gain: _____ BTU/h

2.14 Design Total Heat Gain: _____ BTU/h

2.15 Design Total Heat Loss: _____ BTU/h

2.16 Design Airflow: ¹³ _____ CFM

2.17 Design Duct Static Pressure: ¹⁴ _____ in. Water Column

2.18 Full Load Calculations Report Attached: Yes No

3. Selected Cooling Equipment, if Cooling Equipment to be Installed

3.1 Condenser Manufacturer & Model: _____

3.2 Evaporator / Fan Coil Manufacturer & Model: _____

3.3 AHRI Reference #: _____

3.4 Listed Efficiency: _____ EER _____ SEER _____

3.5 Heating Coefficient of Performance (COP): _____

3.6 Refrigerant Type: R-410a R-410a Other _____

3.7 Fan Speed Type: Fixed Variable (ECM/ICM) Other _____

3.8 Listed Sys. Latent Capacity at Design Cond.: _____ BTU/h

3.9 Listed Sys. Total Capacity at Design Cond.: _____ BTU/h

3.10 Listed Sys. Latent Capacity (Value 3.8) ÷ Design Latent Heat Gain (Value 2.12), ENERGY STAR certified dehumidifier installed: Yes No

3.11 If Listed Sys. Latent Capacity (Value 3.8) ÷ Design Latent Heat Gain (Value 2.12) is 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size: Yes No

3.12 Listed Sys. Total Capacity (Value 3.10) ÷ 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size: Yes No

3.13 AHRI Certificate Attached: Yes No

4. Selected Heat Pump Equipment, if Heatpump to be Installed

4.1 AHRI Listed Efficiency: _____ HSPF or Ground Source COP _____

4.2 Performance at 17°F: Capacity _____ BTU/h Efficiency _____ COP ¹¹

4.3 Performance at 47°F: Capacity _____ BTU/h Efficiency _____ COP ¹¹

- Check "Yes" if this system is to handle temporary occupant loads
- Such a system may be required to accommodate a significant number of guests on a regular or sporadic basis and shall be handled by a supplemental cooling system
 - (e.g., a small, single-package unit or split-coil unit) or by a system that can shift capacity from zone to zone (e.g., a variable volume system)

We should hardly ever see this

HVAC System Contractor Checklist Section #1

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
 HVAC System Quality Installation Contractor Checklist ¹

Home Address: _____ City: _____ State: _____ Zip Code: _____

System Description: _____ Cooling system for temporary occupant load? Yes No

1. Whole-Building Mechanical Ventilation Design ⁶	Builder Verified ⁷	Cost Verified ⁸	N/A
1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5 ⁷	<input type="checkbox"/>	<input type="checkbox"/>	-
1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate intermittently and automatically based on a timer and to restrict outdoor air intake when not in use (e.g., motorized damper).	<input type="checkbox"/>	<input type="checkbox"/>	-
1.3 Documentation is attached with ventilation system type, location, design rate, and frequency and duration of each ventilation cycle.	<input type="checkbox"/>	<input type="checkbox"/>	-
1.4 If present, continuously-operating vent. & exhaust fans designed to operate during all occupiable hours.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 If present, intermittently-operating whole-house ventilation system designed to automatically operate at least once per day and at least 10% of every 24 hours.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

2. Heating & Cooling System Design ⁹ - Parameters used in the design calculations shall reflect home to be built, specifically, outdoor design temperature, wind orientation, number of facades, conditioned floor area, window area, predominant window performance and occupant loads, infiltration rate, mechanical ventilation rate, presence of AER, FV or better filter, and indoor temperature setpoints = 70°F for heating, 78°F for cooling

2.1 Heat Loss / Gain Method: Manual #8 2006 ASHRAE Other: _____ | | |

2.2 Duct On/Off Method: Manual OEM Rec. Other: _____ | | |

2.3 Equipment Selection Method: Manual OEM Rec. Other: _____ | | |

2.4 Outdoor Design Temperature: ¹⁰ Location: _____ 1%: _____ °F 99%: _____ °F | | |

2.5 Orientation of Rated Home (e.g., North, South): _____ | | |

2.6 Number of Occupants Served by System: ¹¹ _____ | | |

2.7 Conditioned Floor Area in Rated Home: _____ Sq. Ft. | | |

2.8 Window Area in Rated Home: _____ Sq. Ft. | | |

2.9 Predominant Window SHGC in Rated Home: ¹² _____ | | |

2.10 Infiltration Rate in Rated Home: ¹³ Summer: _____ Winter: _____ | | |

2.11 Mechanical Ventilation Rate in Rated Home: _____ CFM | | |

2.12 Design Latent Heat Gain: _____ BTU/h | | |

2.13 Design Sensible Heat Gain: _____ BTU/h | | |

Footnote #4

- The person responsible for the heating, cooling, and ventilation design shall be responsible for completing Sections 1 and 2 of this Checklist

1. Whole-Building Mechanical Ventilation Design ⁶

- 1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5. ⁷
- 1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate intermittently and automatically based on a timer and to restrict outdoor air intake when not in use (e.g., motorized damper).
- 1.3 Documentation is attached with ventilation system type, location, design rate, and frequency and duration of each ventilation cycle.
- 1.4 If present, continuously-operating vent. & exhaust fans designed to operate during all occupiable hours.
- 1.5 If present, intermittently-operating whole-house ventilation system designed to automatically operate at least once per day and at least 10% of every 24 hours.

HVAC Contractor Checklist

1. Whole-Building Mechanical Ventilation

1.1 Ventilation system installed has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5

Footnote: #7

- The system shall have at least one supply or exhaust fan with associated ducts and controls
- Local exhaust fans are allowed to be part of an exhaust ventilation system
- Outdoor air ducts connected to the return side of an air handler are allowed to be part of a supply ventilation system if manufacturer requirements for return air temperature are met



Can a House Be Too Tight?

NO!


- Wrong question
- Control **air flow**
- In order to control the air

Real question

- Can houses be under-ventilated?

YES!

Build Tight and Ventilate Right



American Society of Heating, Refrigerating,
and Air-Conditioning Engineers

Whole-Building Mechanical Ventilation Design

ASHRAE Standard 62.2 - 2010

- Standard for establishing consistent ventilation in a house
- Both Whole House **Controlled Mechanical Ventilation** and **Spot ventilation** standard
- This standard applies to spaces intended for human occupancy within **single-family houses and multifamily structures of three stories or fewer** above grade, including manufactured and modular houses



Local Exhaust or “Spot Ventilation” Ventilation Removes pollutants, Moisture, and odors at their source

•Baths:

- 50 CFM intermittent
- 20 CFM continuous



•Kitchens:

- 100 CFM intermittent
- 25 CFM continuous
- Ducted to outside



WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM AIRFLOW RATE REQUIREMENTS

DWELLING UNIT FLOOR AREA (square feet)	NUMBER OF BEDROOMS				
	0 – 1	2 – 3	4 – 5	6 – 7	> 7
< 1,500	30	45	60	75	90
1,501 – 3,000	45	60	75	90	105
3,001 – 4,500	60	75	90	105	120
4,501 – 6,000	75	90	105	120	135
6,001 – 7,500	90	105	120	135	150
> 7,500	105	120	135	150	165

- ASHRAE 62.2 Table or Formula:
- Ventilation calculated by formula:

$$\text{Fan flow (CFM)} = 0.01 \text{ CFM} \times \text{your floor area} + 7.5 \times (\text{your number of bedrooms} + 1)$$

- For a 1,510 square foot 4-bedroom home,
 - (0.01 X 1510) + (7.5 times 5)
 - Formula Result: 52.5 CFM
 - Chart Result: 75 CFM

EnergyLogic Use the Formula:

Rater-measured ventilation rate is within 100-120% of design value



Pick Your Ventilation Strategy Carefully to Maximize Performance


Built Tight Ventilate Right

Three Strategies



- Supply Ventilation
(Furnace blower must be ECM/ICM)
- Exhaust Ventilation
 - Possible configuration with reversed dampered designed opening to outside
- Balanced Ventilation


ULTRAGREEN DC MOTOR TECHNOLOGY
WhisperGreen
ELECTRONIC EXIST



There must be a control



Adjustable fan control highly recommended



Motion sensor



This controls the ventilation system

Recommend not turning off



HVAC Contractor Checklist

1. Whole-Building Mechanical Ventilation

Supply side ventilation:

- 1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate intermittently and automatically based on a timer and to restrict outdoor air intake when not in use (**e.g., motorized damper**)
- Footnote: #16
 - If the whole-house ventilation system utilizes the HVAC air handler, **then the fan speed type shall be ECM / ICM, variable speed, and run at a reduced speed during ventilation, or**
 - Include a controller (e.g., smart cycler) that reduces the ventilation run time by accounting for hours when HVAC system is heating or cooling the home



HVAC Contractor Checklist

1. Whole-Building Mechanical Ventilation

- 1.3 **Documentation is attached with ventilation system type:**
 - Location
 - design rate,
 - Frequency and duration of each ventilation cycle
- 1.4 If present, continuously-operating vent. & exhaust fans designed to operate during all occupiable hours
- 1.5 If present, intermittently-operating whole-house ventilation system designed to automatically operate at least once per day and at least 10% of every 24 hour period



Ventilation's Impact on the HERS Index

- The Home will not receive the energy benefit of building tighter than .35 NACH unless the house also has a controlled whole house mechanical ventilation

- This is do to the RESNET and Energy Code Reference home which the Rated home is compared to
- Fan energy (watts) impacts the ability to fully take advantage of the trade offs for code and compliance for ESv3
 - Consider low watt draw ventilation strategies to lower the HERS Index
 - Furnace blowers are not low watt draw fans

Home Energy Rating Certificate
 5 Stars Plus
 Confirmed Rating

Estimated Annual Energy Cost

Use	HERS Index	Cost	Percent
Heating	16.1	\$455	39%
Cooling	2.6	\$74	1%
Hot Water	19.2	\$515	7%
Light/Electronics	16.1	\$455	39%
Refrigeration	6.5	\$181	15%
Water Heating	16.1	\$455	39%
Total	114.8	\$3135	100%

Mechanical System Analysis

System	Manufacturer	Model	Capacity	Efficiency
Heating	Furnace	Model	100,000 BTU/hr	80%
Cooling	Air Conditioning	Model	36,000 BTU/hr	13 SEER
Water Heating	Water Heater	Model	40 Gallons	0.68 EF



HVAC System Contractor Checklist Section #2

2. Heating & Cooling System Design

- Parameters used in the design calculations **shall** reflect home to be built – specifically:
 - Outdoor design temperatures
 - Home orientation
 - Number of bedrooms
 - Conditioned floor area
 - Window area
 - Predominant window U-value and SHGC
 - Insulation R-values
 - Infiltration rate
 - Mechanical ventilation rate
 - Presence of MERV6 or better filter
 - Indoor temperature set-points
 - 70°F for heating; 75°F for cooling

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist

Home Address: _____ City: _____ State: _____ Zip Code: _____


System Description: _____ Cooling system for temporary occupant use? Yes No

Item	Builder Verified	Contractor Verified	N/A
1. Whole-Building Mechanical Ventilation Design			
1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5.	<input type="checkbox"/>	<input type="checkbox"/>	-
1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate automatically and automatically based on a timer and to restrict outdoor air intake when not in use (e.g., motorized damper).	<input type="checkbox"/>	<input type="checkbox"/>	-
1.3 Documentation is attached with ventilation system type, location, design rate, and frequency and duration of each ventilation cycle.	<input type="checkbox"/>	<input type="checkbox"/>	-
1.4 If present, continuously-operating vent, & exhaust fans designed to operate during all occupiable hours.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 If present, intermittently-operating, whole-house ventilation system designed to automatically operate at least once per day and at least 15% of every 24 hours.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. Heating & Cooling System Design - Parameters used in the design calculations shall reflect home to be built, specifically, outdoor design temperatures, home orientation, number of bedrooms, conditioned floor area, window area, predominant window performance and insulation levels, infiltration rate, mechanical ventilation rate, presence of MERV6 or better filter, and indoor temperature setpoints = 70°F for heating, 75°F for cooling.			
2.1 Heat Loss / Gain Method: <input type="checkbox"/> Manual v.18 <input type="checkbox"/> 2009 ASHRAE <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.2 Duct Design Method: <input type="checkbox"/> Manual D <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.3 Equipment Selection Method: <input type="checkbox"/> Manual S <input type="checkbox"/> OEM Rec <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.4 Outdoor Design Temperatures: * Location: _____ 1% _____ °F 99% _____ °F	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.5 Orientation of Rated Home (e.g., North, South): _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.6 Number of Occupants Served by System: **	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.7 Conditioned Floor Area in Rated Home: _____ Sq. Ft.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.8 Window Area in Rated Home: _____ Sq. Ft.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.9 Predominant Window SHGC in Rated Home: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.10 Infiltration Rate in Rated Home: ** Summer: _____ Winter: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.11 Mechanical Ventilation Rate in Rated Home: _____ CFM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.12 Design Latent Heat Gain: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.13 Design Sensible Heat Gain: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.14 Design Total Heat Gain: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.15 Design Total Heat Loss: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.16 Design Airflow: ** _____ CFM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.17 Design Duct Static Pressure: ** _____ In. Water Column	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.18 Full Load Calculations Report Attached:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.1 If Listed Sys. Latent Capacity (Value 3.8) > Design Latent Heat Gain (Value 2.12), ENERGY STAR certified dehumidifier installed	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.12 Listed Sys. Total Capacity (Value 3.10) is 85-115% of Design Total Heat Gain (Value 2.14) or next nominal size	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.10 AHRI Certificate Attached:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. Selected Heat Pump Equipment, if Heatpump to be installed			
4.1 AHRI Listed Efficiency: _____ HSPF or Ground-Source COP	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Performance at 17°F: Capacity _____ BTU/h Efficiency _____ COP ²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.3 Performance at 47°F: Capacity _____ BTU/h Efficiency _____ COP ²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Thermal Enclosure Systems Rater Checklist

Giving the HVAC Contractor something they have never had before

- Defined Thermal Boundary
 - Air barrier and thermal barrier alignment
- RESNET Grade 1 insulation
 - Use the actual R-values
 - U-values and SHHC
- Air sealing
 - Tight Envelopes
- Control
 - Air Flow
 - Moisture Flow
 - Thermal Flow



ESv3 Design for House Plans with Multiple Configurations: (e.g., plan, elevation, option, and orientation)

2. Heating & Cooling System Design ^{8.8}. Parameters used in the design calculations shall reflect home to be built, specifically, outdoor design temperatures, home orientation, number of bedrooms, conditioned floor area, window area, predominant window performance and insulation levels, infiltration rate, mechanical ventilation rate, presence of MERV6 or better filter, and indoor temperature setpoints = 70°F for heating; 75°F for cooling.

Footnote #8

- Heating and cooling loads shall be calculated, equipment shall be selected, and duct systems shall be sized according to...
 - The latest editions of ACCA Manuals J, S, & D
 - 2009 ASHRAE Handbook of Fundamentals
 - Or a substantively equivalent procedure
- The HVAC system design shall be completed for **the specific configuration** (e.g., plan, elevation, option, and orientation) of the home to be built except as permitted herein:

Footnote: #8 ESv3 Design for House Plans with Multiple Configurations: (e.g., plan, elevation, option, and orientation)


- The **load shall be completed for each configuration**
- If the loads across configurations vary by $\leq 25\%$ then the largest load can be used subject to oversize rules established by Manual S
- Otherwise, the contractor shall group the load for each configuration into a set with $\leq 25\%$ variation and equipment selection shall be completed for each set of loads
- **Designed air flow**
 - Room level designed air flows shall be done for each configuration unless air flows across configurations vary by $\leq 25\%$ or 25 CFM then the average shall be permitted
 - Otherwise, the contractor shall group the room-level design airflow for each configuration into a set with $\leq 25\%$ or 25 CFM variation and the duct design shall be completed for the average airflow of that set.



What does this mean?

Foundation Types	Full Basement	Base / Crawl	Walkout	Crawl / Walkout	Full Crawl		Elevations that change SQ or volume
Orientations	How many potential configurations are there?					Options	
North						3 bedroom	Elev. A
NE						4 Bedroom	Elev. B
East						Office/bed room	Elev. C
SE							Elev. D
South							
SW							
West							
NW							

Batching in set that at $\leq 25\%$



Start with Template Mover to Sit Specific





Site Specific Design

- Rater Checklist
- For each house plan with multiple configurations (e.g., orientations, elevations, options)
- The Rater shall confirm that the parameters listed in Items 1.2.2 to 1.2.6 are aligned with the rated home



HVAC SYSTEM QUALITY INSTALLATION Checklist is AC Centric





HVAC Contractor's Checklist

2. Heating & Cooling System Design ^{4,8} - Parameters used in the design calculations shall reflect home to be built, specifically, outdoor design temperatures, home orientation, number of bedrooms, conditioned floor area, window area, predominant window performance and insulation levels, infiltration rate, mechanical ventilation rate, presence of MERV6 or better filter, and indoor temperature setpoints = 70°F for heating, 75°F for cooling.

2.1 Heat Loss / Gain Method:	<input type="checkbox"/> Manual J v8 <input type="checkbox"/> 2009 ASHRAE <input type="checkbox"/> Other: _____	<input type="checkbox"/>	<input type="checkbox"/>	-
2.2 Duct Design Method:	<input type="checkbox"/> Manual D <input type="checkbox"/> Other: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.3 Equipment Selection Method:	<input type="checkbox"/> Manual S <input type="checkbox"/> OEM Rec. <input type="checkbox"/> Other: _____	<input type="checkbox"/>	<input type="checkbox"/>	-
2.4 Outdoor Design Temperatures: ⁹ Location: _____	1%: ___ °F 99%: ___ °F	<input type="checkbox"/>	<input type="checkbox"/>	-
2.5 Orientation of Rated Home (e.g., North, South):	_____	<input type="checkbox"/>	<input type="checkbox"/>	-
2.6 Number of Occupants Served by System: ¹⁰	_____	<input type="checkbox"/>	<input type="checkbox"/>	-
2.7 Conditioned Floor Area in Rated Home:	_____ Sq. Ft.	<input type="checkbox"/>	<input type="checkbox"/>	-
2.8 Window Area in Rated Home:	_____ Sq. Ft.	<input type="checkbox"/>	<input type="checkbox"/>	-
2.9 Predominant Window SHGC in Rated Home: ¹¹	_____	<input type="checkbox"/>	<input type="checkbox"/>	-
2.10 Infiltration Rate in Rated Home: ¹²	Summer: _____ Winter: _____	<input type="checkbox"/>	<input type="checkbox"/>	-
2.11 Mechanical Ventilation Rate in Rated Home:	_____ CFM	<input type="checkbox"/>	<input type="checkbox"/>	-
2.12 Design Latent Heat Gain:	_____ BTUh	<input type="checkbox"/>	<input type="checkbox"/>	-
2.13 Design Sensible Heat Gain:	_____ BTUh	<input type="checkbox"/>	<input type="checkbox"/>	-
2.14 Design Total Heat Gain:	_____ BTUh	<input type="checkbox"/>	<input type="checkbox"/>	-
2.15 Design Total Heat Loss:	_____ BTUh	<input type="checkbox"/>	<input type="checkbox"/>	-
2.16 Design Airflow: ¹³	_____ CFM	<input type="checkbox"/>	<input type="checkbox"/>	-
2.17 Design Duct Static Pressure: ¹⁴	_____ In. Water Column	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.18 Full Load Calculations Report Attached		<input type="checkbox"/>	<input type="checkbox"/>	-

Footnote: #9

Design Information

Weather: Denver, CO, US

Winter Design Conditions	Summer Design Conditions
Outside db: -3 °F Inside db: 65 °F Design TD: 73 °F	Outside db: 90 °F Inside db: 75 °F Design TD: 15 °F Daily range: H Relative humidity: 50 % Moisture difference: -36 gr/lb

2.4 Outdoor Design Temperatures: ⁹ Location: _____ 1%: ___ °F 99%: ___ °F

- If the design conditions are dictated by a code, then code requirements rule **(We are getting better at recognizing this)**
- Otherwise, the default values shall be used
- The values for the geographically closest location shall be selected or a justification provided for the selected location

Location	Elevation Feet	Latitude Degrees North	Winter		Summer					
			Heating 99% Dry Bulb	Cooling 1% Dry Bulb	Coincide nt Wet Bulb	Design Grains 55% RH	Design Grains 50% RH	Design Grains 45% RH	Daily Range (DR)	
Colorado										
Alamosa AP	7543	37	-11	82	55	-53	-46	-40	H	
Boulder	5358	40	0	91	59	-47	-40	-34	H	
Colorado Springs AP	6171	38	4	87	58	-46	-39	-33	H	
Craig	6283	40	-12	85	56	-52	-45	-39	H	
Denver AP	5283	39	-3	90	59	-46	-39	-33	H	

Footnotes: #10


2.6 Number of Occupants Served by System: ¹⁰

- The number of occupants among all HVAC systems in the home must be equal to the number of bedrooms, as defined below, plus one (a Ventilation issue)
- Occupants listed for systems serving temporary occupant loads, as described in Footnote 3, shall be permitted to exceed this limit (Discussed before)
- **A bedroom is defined by RESNET** as a room or space 70 sq. ft. or greater size, with egress window and closet, used **or intended to be used for sleeping**
- A "den", "library", or "home office" with a closet, egress window, and 70 sq. ft. or greater size or other similar rooms shall count as a bedroom, but living rooms and foyers shall not
 - An egress window, as defined in 2009 IRC section R310, shall refer to any operable window that provides for a means of escape and access for rescue in the event of an emergency. The egress window shall:
 - have a sill height of not more than 44 inches above the floor; AND
 - have a minimum net clear opening of 5.7 sq. ft.; AND
 - have a minimum net clear opening height of 24 in.; AND
 - have a minimum net clear opening width of 20 in.; AND
 - be operational from the inside of the room without the use of keys, tools or special knowledge

Footnotes: #11

2.9 Predominant Window SHGC in Rated Home: ¹¹

“Predominant” is defined as the SHGC value used in the greatest amount of window area in the home.

 World's Best Window Co. Millennium 2000+ Vinyl-Clad Wood Frame Double Glazing - Argon Fill - Low E Product Type: Vertical Slider	
ENERGY PERFORMANCE RATINGS	
U-Factor (U.S./I-P)	Solar Heat Gain Coefficient
0.30	0.30
ADDITIONAL PERFORMANCE RATINGS	
Visible Transmittance	Air Leakage (U.S./I-P)
0.51	0.2
Condensation Resistance	
51	—
<small>Manufacturer stipulates that these ratings conform to applicable NFRC procedures for determining whole product performance. NFRC ratings are determined for a fixed set of environmental conditions and a specific product size. NFRC does not recommend any product and does not warrant the suitability of any product for any specific use. Consult manufacturer's literature for other product performance information. www.nfrc.org</small>	



Footnotes: #12

2.10 Infiltration Rate in Rated Home: ¹²

- Infiltration rate shall reflect value used in confirmed or projected HERS rating for rated home
- Alternatively, use “Average” or “Semiloose” values for the cooling season infiltration rates and “Semi-tight” or “Average” values for the heating season infiltration rates, as defined by ACCA Manual J, Eighth Edition, Version Two



Infiltration:

Method
Construction quality
Fireplaces

Simplified
Average
0



Footnotes: #13

2.16 Design Airflow: ¹³

Cooling Equipment Summary

Make	Carrier	
Trade	Base 13 Puron AC	
Cond	24ABA324A30	
Coil	CAP**2414A**++TDR	
ARI ref no.	738723	
Efficiency	11.6 EER, 13 SEER	
Sensible cooling	18148	Btuh
Latent cooling	3203	Btuh
Total cooling	21350	Btuh
Actual air flow	995	cfm
Air flow factor	0.063	cfm/Btuh
Static pressure	0.70	in H2O
Load sensible heat ratio	1.00	

- Design airflow is the design value(s) for the blower in CFM, as determined by using the manufacturer's expanded performance data to select equipment, per ACCA **Manual S** procedures.



Footnotes: #14

2.17 Design Duct Static Pressure: ¹⁴

Cooling Equipment Summary

Make	Carrier	
Trade	Base 13 Puron AC	
Cond	24ABA324A30	
Coil	CAP**2414A**++TDR	
ARI ref no.	738723	
Efficiency	11.6 EER, 13 SEER	
Sensible cooling	18148	Btuh
Latent cooling	3203	Btuh
Total cooling	21350	Btuh
Actual air flow	995	cfm
Air flow factor	0.063	cfm/Btuh
Static pressure	0.70	in H2O
Load sensible heat ratio	1.00	

- Design duct static pressure shall account for the installation of a MERV 6 or higher filter.



HVAC Rater's Checklist

Raters are required to review the following

1. Review of HVAC System Quality Installation Contractor Checklist ²			
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), AHRI certificate (3.15), and balancing report (10.2).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist Item # indicated in parenthesis): ³			
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location ⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 Home orientation (2.5) matches orientation of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.3 Number of occupants (2.6) equals number of occupants in rated home ⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.4 Conditioned floor area (2.7) is within ±10% of conditioned floor area of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.5 Window area (2.8) is within ±10% of calculated window area of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.6 Predominant window SHGC (2.9) is within 0.1 of predominant value in rated home ⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.7 Listed latent cooling capacity (3.10) exceeds design latent heat gain (2.12)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.8 Listed sensible cooling capacity (3.11) exceeds design sensible heat gain (2.13)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.12) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size ⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.3, 5.1), and AHRI certificate or OEM catalog data all match ⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temp. (as determined using pressure / temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees) ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) or superheat (6.6 minus 7.5) value equals reported target subcooling (7.3) or superheat (7.7) temperature ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Rater-verified supply & return duct static pressure ≤ 110% of contractor values (9.3, 9.4)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

HVAC Contractor Checklist Section #3



ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist¹

Home Address: _____ City: _____ State: _____ Zip Code: _____
System Description:¹ _____ Cooling system for temporary occupant load? ² Yes No

3. Selected Cooling Equipment, If Cooling Equipment to be Installed			
3.1 Condenser Manufacturer & Model:	_____	<input type="checkbox"/>	<input type="checkbox"/>
3.2 Evaporator / Fan Coil Manufacturer & Model:	_____	<input type="checkbox"/>	<input type="checkbox"/>
3.3 AHRI Reference #: ¹⁶	_____	<input type="checkbox"/>	<input type="checkbox"/>
3.4 Listed Efficiency:	EER _____ SEER _____	<input type="checkbox"/>	<input type="checkbox"/>
3.5 Metering Device Type:	<input type="checkbox"/> TXV <input type="checkbox"/> Fixed orifice <input type="checkbox"/> Other: _____	<input type="checkbox"/>	<input type="checkbox"/>
3.6 Refrigerant Type:	<input type="checkbox"/> R-410a <input type="checkbox"/> Other: _____	<input type="checkbox"/>	<input type="checkbox"/>
3.7 Fan Speed Type: ¹⁷	<input type="checkbox"/> Fixed <input type="checkbox"/> Variable (ECM / ICM) <input type="checkbox"/> Other: _____	<input type="checkbox"/>	<input type="checkbox"/>
3.8 Listed Sys. Latent Capacity at Design Cond.: ¹⁸	_____ BTUh	<input type="checkbox"/>	<input type="checkbox"/>
3.9 Listed Sys. Sensible Capacity at Design Cond.: ¹⁸	_____ BTUh	<input type="checkbox"/>	<input type="checkbox"/>
3.10 Listed Sys. Total Capacity at Design Cond.: ¹⁸	_____ BTUh	<input type="checkbox"/>	<input type="checkbox"/>
3.11 If Listed Sys. Latent Capacity (Value 3.8) ≤ Design Latent Heat Gain (Value 2.12), ENERGY STAR certified dehumidifier installed		<input type="checkbox"/>	<input type="checkbox"/>
3.12 Listed Sys. Total Capacity (Value 3.10) is 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size ^{6, 19}		<input type="checkbox"/>	<input type="checkbox"/>
3.13 AHRI Certificate Attached ¹⁶		<input type="checkbox"/>	<input type="checkbox"/>
2.17 Design Duct Static Pressure: ¹⁴ _____ in. Water Column <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>			
2.18 Full Load Calculations Report Attached ¹¹ <input type="checkbox"/>			
3. Selected Cooling Equipment, If Cooling Equipment to be Installed			
Condenser Manufacturer & Model: _____ <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>			
Evaporator / Fan Coil Manufacturer & Model: _____ <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>			
3.3 AHRI Reference #: ¹⁶ _____ <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>			
3.4 Listed Efficiency: EER _____ SEER _____ <input type="checkbox"/> <input type="checkbox"/>			
3.5 Metering Device Type: <input type="checkbox"/> TXV <input type="checkbox"/> Fixed orifice <input type="checkbox"/> Other: _____ <input type="checkbox"/> <input type="checkbox"/>			
3.6 Refrigerant Type: <input type="checkbox"/> R-410a <input type="checkbox"/> Other: _____ <input type="checkbox"/> <input type="checkbox"/>			
3.7 Fan Speed Type: ¹⁷ <input type="checkbox"/> Fixed <input type="checkbox"/> Variable (ECM / ICM) <input type="checkbox"/> Other: _____ <input type="checkbox"/> <input type="checkbox"/>			
3.8 Listed Sys. Latent Capacity at Design Cond.: ¹⁸ _____ BTUh <input type="checkbox"/> <input type="checkbox"/>			
3.9 Listed Sys. Sensible Capacity at Design Cond.: ¹⁸ _____ BTUh <input type="checkbox"/> <input type="checkbox"/>			
3.10 Listed Sys. Total Capacity at Design Cond.: ¹⁸ _____ BTUh <input type="checkbox"/> <input type="checkbox"/>			
3.11 If Listed Sys. Latent Capacity (Value 3.8) ≤ Design Latent Heat Gain (Value 2.12), ENERGY STAR certified dehumidifier installed <input type="checkbox"/> <input type="checkbox"/>			
3.12 Listed Sys. Total Capacity (Value 3.10) is 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size ^{6, 19} <input type="checkbox"/> <input type="checkbox"/>			
3.13 AHRI Certificate Attached ¹⁶ <input type="checkbox"/> <input type="checkbox"/>			
4. Selected Heat Pump Equipment, If Heatpump to be Installed			
4.1 AHRI Listed Efficiency: _____ HSPF or Ground-Source _____ COP <input type="checkbox"/> <input type="checkbox"/>			
4.2 Performance at 17°F: Capacity _____ BTUh Efficiency _____ COP ¹¹ <input type="checkbox"/> <input type="checkbox"/>			
4.3 Performance at 47°F: Capacity _____ BTUh Efficiency _____ COP ¹¹ <input type="checkbox"/> <input type="checkbox"/>			

Selected Cooling Equipment if installed

Footnotes: #16

3.3 AHRI Reference # ¹⁶

3.13 AHRI Certificate Attached ¹⁶



- All evaporators and condensing units shall be properly matched as demonstrated by an attached AHRI certificate
- If an AHRI certificate is not available, a copy of OEM-provided catalog data indicating acceptable combination selection and performance data shall be attached



Footnotes: #17

3.7 Fan Speed Type ¹⁷ Fixed Variable (ECM / ICM) Other: _____

- If the whole-house ventilation system utilizes the HVAC air handler, then the fan speed type shall be ECM / ICM, variable speed, and run at a reduced speed during ventilation
- Or include a controller (e.g., smart cyclor) that reduces the ventilation run time by accounting for hours when HVAC system is heating or cooling the home



Footnotes: #18

3.8 Listed Sys. Latent Capacity at Design Cond.: ⁽¹⁸⁾ _____ BTUh
 3.9 Listed Sys. Sensible Capacity at Design Cond.: ⁽¹⁸⁾ _____ BTUh
 3.10 Listed Sys. Total Capacity at Design Cond.: ⁽¹⁸⁾ _____ BTUh

Cooling Equipment Summary

Make	Carrier
Trade	Base 13 Puron AC
Cond	24ABA324A30
Coil	CAP**2414A**++TDR
ARI ref no.	738723
Efficiency	11.6 EER, 13 SEER
Sensible cooling	18148 Btuh
Latent cooling	3203 Btuh
Total cooling	21350 Btuh
Actual air flow	995 cfm
Air flow factor	0.063 cfm/Btuh
Static pressure	0.70 in H ₂ O
Load sensible heat ratio	1.00

- Listed system capacity at design conditions is to be obtained from the OEM expanded performance data



Footnotes: #8, #19

3.12 Listed Sys. Total Capacity (Value 3.10) is 95-115% of Design Total Heat Gain (Value 2.14) or next nominal size ^(8,19)

#8 – Sizing requirements for houses with multiple orientations

#19 - For cooling systems

- The next largest nominal piece of equipment may be used that is available to satisfy the latent and sensible requirements**
- Single-speed systems generally have OEM nominal size increments of ½ ton
- Multi-speed or multi-stage equipment may have OEM nominal size increments of one ton
- Therefore, the use of these advanced system types can provide extra flexibility to meet the equipment sizing requirements



HVAC System Contractor Checklist Section #4

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist ¹

Home Address: _____ City: _____ State: _____ Zip Code: _____
System Description: _____ Cooling system for temporary occupant load? Yes No

Item	Builder Verified	Cost Verified	N/A
1. Whole-Building Mechanical Ventilation Design ¹			
1.1 Ventilation system installed that has been designed to meet ASHRAE 62.2-2010 requirements including, but not limited to, requirements in Items 1.2-1.5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2 Ventilation system does not utilize an intake duct to the return side of the HVAC system unless the system is designed to operate intermittently and automatically based on a timer and to restrict outdoor air intake when not in use (e.g., motorized damper)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Documentation is attached with ventilation system type, location, design rate, and frequency and duration of each ventilation type	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4 If present, continuously-operating vent. & exhaust fans designed to operate during all occupiable hours	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 If present, intermittently-operating whole-house ventilation system designed to automatically operate at least once per day and at least 10% of every 24 hours	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. Heating & Cooling System Design ² - Parameters used in the design callout(s) shall reflect home to be built, specifically, outdoor design temperature, home orientation, number of bedrooms, conditioned floor area, window area, predominant window performance and insulation levels, infiltration rate, mechanical ventilation rate, presence of AHRV or better filter, and indoor temperature setpoints +79°F for heating, 79°F for cooling			
2.1 Heat Loss / Gain Method: <input type="checkbox"/> Manual <input type="checkbox"/> ASHRAE <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.2 Duct Design Method: <input type="checkbox"/> Manual <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.3 Equipment Selection Method: <input type="checkbox"/> Manual <input type="checkbox"/> OEM Rec. <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.4 Outdoor Design Temperature: ³ Location: _____ °F _____ °F _____ °F	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.5 Orientation of Rated Home (e.g., North, South): _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.6 Number of Occupants Served by System: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.7 Conditioned Floor Area in Rated Home: _____ Sq. Ft.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.8 Window Area in Rated Home: _____ Sq. Ft.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.9 Predominant Window SHGC in Rated Home: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.10 Infiltration Rate in Rated Home: _____ Summer: _____ Winter: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.11 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.12 AHRI Efficiency _____ EER _____ SEER _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.13 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.14 Metering Device Type: <input type="checkbox"/> TXV <input type="checkbox"/> Fixed orifice <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.15 Refrigerant Type: <input type="checkbox"/> R-410a <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.16 Refrigerant Type: <input type="checkbox"/> Fixed <input type="checkbox"/> Variable (ECM/ICM) <input type="checkbox"/> Other	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.17 Latent Capacity at Design Cond.: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.18 Listed Sensible Capacity at Design Cond.: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.19 Listed Sensible Capacity at Design Cond.: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.20 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.21 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.22 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.23 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.24 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.25 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.26 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.27 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.28 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.29 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.30 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.31 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.32 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.33 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.34 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.35 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.36 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.37 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.38 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.39 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.40 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.41 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.42 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.43 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.44 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.45 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.46 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.47 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.48 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.49 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.50 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.51 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.52 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.53 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.54 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.55 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.56 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.57 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.58 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.59 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.60 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.61 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.62 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.63 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.64 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.65 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.66 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.67 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.68 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.69 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.70 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.71 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.72 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.73 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.74 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.75 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.76 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.77 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.78 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.79 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.80 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.81 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.82 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.83 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.84 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.85 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.86 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.87 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.88 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.89 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.90 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.91 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.92 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.93 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.94 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.95 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.96 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.97 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.98 AHRI Certificate # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.99 AHRI Efficiency _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.100 AHRI Reference # _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

4. Selected Heat Pump Equipment, If Heatpump to be Installed

4.1 AHRI Listed Efficiency: _____ HSPF

4.2 Performance at 17°F: Capacity _____ BTU/h Efficiency: _____ COP

4.3 Performance at 47°F: Capacity _____ BTU/h Efficiency: _____ COP

HVAC Contractor Checklist Section #5


ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist ¹

Home Address: _____ City: _____ State: _____ Zip Code: _____
System Description: _____ Cooling system for temporary occupant load? Yes No

Item	Builder Verified	Cost Verified	N/A
3. Selected Furnace, If Furnace to be Installed			
3.1 Furnace Manufacturer & Model: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.2 Listed Efficiency: _____ AFUE	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.3 Listed Output Heating Capacity: _____ BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.4 Listed Output Heat. Cap. (Value 3.3) is 100-140% of Design Total Heat Loss (Value 2.15) or next nominal size ^{2,21}	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.8 Value 7.4 is a 2 F or Value 7.8 is a 5 F	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.9 An OEM and procedure (e.g., an add-on for a ground-source heat pump) has been used in place of sub-cooling or super-heat process and documentation has been attached that defines the procedure	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. Electrical Measurements - Taken at electrical disconnect while powered on or operation			
8.1 Evaporator or furnace air handler fan: _____ amperage _____ line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.2 Condenser unit: _____ amperage _____ line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.3 Electrical measurements within OEM-specified tolerance of nameplate value	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. Air Flow Tests			
9.1 Air volume at evaporator _____ CFM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Test performed in which mode? <input type="checkbox"/> Heating <input type="checkbox"/> Cooling	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Return duct static pressure: _____ S/WC Test Hole Location: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.4 Supply duct static pressure: _____ S/WC Test Hole Location: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.5 Test hole locations are well-marked and accessible ¹⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.6 Airflow volume at evaporator (Value 9.1), at fan design speed and full operating load, a 15% of the airflow required per system design (Value 2.15) or within range recommended by OEM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. Air Balance			
10.1 Balancing report prepared and attached including the room name and design airflow for each supply and return register. In addition, final individual room airflow measured and documented through one of the following options	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10.1.1 Measured by contractor using ASHRAE 154-2007 protocol, documented by contractor on the balancing report, & verified by contractor to be within the greater of a 20% or 25 CFM of design airflow ¹¹ , OR	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10.1.2 To be measured, documented, and verified by a Rater per Item 1.4.2 of the HVAC System QI Rater Checklist	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. System Controls			
11.1 Operating and safety controls meet OEM requirements	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11.2 Drain pan	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11.3 Corrosion-resistant drain pan, properly sloped to drainage system, included with each HVAC component that produces condensate	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC Company Name: _____ Credentiating Organization: ACCA / A/E / Other _____			
HVAC Contractor Name: _____ HVAC Contractor Signature: _____ Date: _____			
Builder Name: _____ Builder Signature: _____ Date: _____			

Heating Equipment Summary

Make	Carrier
Trade	Carrier
Model	58MCB040-12x
GAMA ID	144278
Efficiency	92.1 AFUE
Heating input	40000 Btu/h
Heating output	33156 Btu/h
Temperature rise	44 °F
Actual air flow	830 cfm
Air flow factor	0.029 cfm/Btu/h
Static pressure	0.70 in H2O
Space thermostat	



Gas Furnace OEM Specs

Temperature Rise: Not required but good idea to measure!

Carrier 58MCB

SPECIFICATIONS (CONTINUED)

UNIT SIZE		080-16	080-20
Shipping Weight - Lb. (KG)		193 (88)	201 (91)
RATINGS AND PERFORMANCE			
Input Btuh*		80,000	80,000
Output Capacity BTUH* (ICS) (Shaded capacities are specified on rating plate)	Direct Vent (2-Pipe)	Upflow	74,000
		Downflow	74,000
		Horizontal	74,000
	Non-Direct Vent (1-Pipe)	Upflow	74,000
		Downflow	74,000
		Horizontal	74,000
AFUE%† Nonweatherized ICS	Direct Vent (2-Pipe)	Upflow	92.3
		Downflow	91.2
		Horizontal	92.1
	Non-Direct Vent (1-Pipe)	Upflow	
		Downflow	
		Horizontal	
Certified Temperature Rise Range °F (°C)		30-60 (17-33)	20-50 (11-28)
Certified External Static Pressure		Heating Cooling	0.15 0.50
Airflow CFM‡		Heating Cooling	1285 1925

Temp rise
30 to 60 F



Footnotes: #8,#21

5.4 Listed Output Heat. Cap. (Value 5.3) is 100-140% of Design Total Heat Loss (Value 2.15) or next nominal size ^{8,21}

#8 – Sizing requirements for houses with multiple orientations

Heating Equipment Summary

Make	Carrier
Trade	Carrier
Model	58MCB040-12x
GAMA ID	144278
Efficiency	92.1 AFUE
Heating input	40000 Btuh
Heating output	33156 Btuh
Temperature rise	44 °F
Actual air flow	830 cfm
Air flow factor	0.029 cfm/Btuh
Static pressure	0.70 in H2O
Space thermostat	

#21 - For warm air heating systems, the output capacity **must be between 100% and 140% of calculated system load** unless a larger size is dictated by the cooling equipment selection



HVAC Contractor Checklist Section #6

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
 HVAC System Quality Installation Contractor Checklist ¹

Refrigerant Tests

- Run system for 15 minutes before testing
- Note: If outdoor ambient temperature at the condenser is $\leq 55^{\circ}\text{F}$ or, if known, below the manufacturer-recommended minimum operating temperature for the cooling cycle, then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6 & 7
- Then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6 & 7

6. Refrigerant Tests - Run system for 15 minutes before testing
 Note: If outdoor ambient temperature at the condenser is $\leq 55^{\circ}\text{F}$ or, if known, below the manufacturer-recommended minimum operating temperature for the cooling cycle, then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6 & 7

6.1 Outdoor ambient temperature at condenser:	___ °F DB	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Return-side air temperature inside duct near evaporator, during cooling mode:	___ °F WB	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Liquid line pressure:	___ psig	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Liquid line temperature:	___ °F DB	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Suction line pressure:	___ psig	<input type="checkbox"/>	<input type="checkbox"/>
6.6 Suction line temperature:	___ °F DB	<input type="checkbox"/>	<input type="checkbox"/>

Footnotes: #22

- Either factory-installed or field-installed TXV's may be used
- For field-installed TXV's, ensure that sensing bulbs are insulated and tightly clamped to the vapor line with good linear thermal contact at the recommended orientation, usually 4 or 8 o'clock



HVAC Contractor Checklist Section #7

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist

8. Selected Furnace, if Furnace to be installed

Item	Pass	Fail	NA
8.1 Furnace Manufacturer & Model	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.2 Listed Efficiency	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.3 Listed Output Heating Capacity	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.4 Listed Output Heat Cap. (Value 5.2) is 100-140% of Design Total Heat Loss (Value 2.15) or heat normal top	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

9. Refrigerant Tests - Run system for 15 minutes before testing

Note: If outdoor ambient temperature at the condenser is $\leq 55^\circ\text{F}$ or, if known, below the manufacturer recommended minimum operating temperature for the cooling cycle, then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6 & 7.

Item	Pass	Fail	NA
9.1 Outdoor ambient temperature at condenser	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Return-air temperature inside duct near evaporator, during cooling mode	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Liquid line pressure	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.4 Liquid line temperature	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.5 Suction line pressure	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.6 Suction line temperature	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

7. Refrigerant Calculations

For System with Thermal Expansion Valve (TXV)

Item	Pass	Fail	NA
7.1 Condenser saturation temperature	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Subcooling value	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 OEM subcooling goal	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Subcooling deviation	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

For System with Fixed Orifice

Item	Pass	Fail	NA
7.5 Evaporator saturation temperature	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.6 Superheat value	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.7 OEM superheat goal	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.8 Superheat deviation	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.9 Value 7.4 is $\pm 3^\circ\text{F}$ or Value 7.8 is $\pm 5^\circ\text{F}$	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>


7.10 An OEM test procedure has been used in place of sub-cooling or super-heat process and documentation has been attached that defines this procedure

Same notes as Section 6:

- Run system for 15 minutes before testing
- Note: If outdoor ambient temperature at the condenser is $\leq 55^\circ\text{F}$ or, if known, below the manufacturer-recommended minimum operating temperature for the cooling cycle
- Then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6 & 7.

Subcooling


- Compressor elevates refrigerant vapor pressure to higher boiling point
- Boiling point higher than outdoor air temperature
- Air across condenser causes refrigerant to condense
- Additional passes in condenser coil cool liquid refrigerant below its boiling point, **to ensure 100% liquid at metering device**
- Subcooling** = amount of refrigerant temperature drop below boiling point to ensure 100% liquid



From the Fluke Digital Library @ www.fluke.com/library

Superheat

- Metering device restricts refrigerant flow, drops refrigerant pressure to new, lower boiling point
- Boiling point lower than indoor air temperature
- Air across evaporator causes refrigerant to boil
- Additional passes in evaporator coil warm gas above its boiling point → ensures 100% gas at compressor
- Superheat = amount of refrigerant temperature rise above boiling point to ensure 100% gas



From the Fluke Digital Library @ www.fluke.com/library

HVAC Contractor Checklist Section #8

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist

Section	Builder/Installer	Quality	W.A.
5. Selected Furnace, if Furnace to be installed			
5.1 Furnace Manufacturer & Model			
5.2 Listed Efficiency			
5.3 Listed Output Heating Capacity			
5.4 Listed Output Heat. Cap. (Value 5.2) is 100-140% of Design Total Heat Loss (Value 2.15) or next nominal size			
6. Refrigerant Tests - Run system for 15 minutes before testing			
6.1 Outdoor ambient temperature at condenser is 18°F or, if known, below the manufacturer recommended maximum operating temperature for the cooling cycle. Then the system shall include a TTY, and the contractor shall mark "N/A" on the Checklist for Section 6 & 7			
6.2 Return-side air temperature inside duct near evaporator, during cooling mode			
6.3 Liquid line pressure			
6.4 Liquid line temperature			
6.5 Suction line pressure			

8. Electrical Measurements – Taken at electrical disconnect while component is in operation

- 8.1 Evaporator or furnace air handler fan: _____ amperage _____ line voltage
- 8.2 Condenser unit: _____ amperage _____ line voltage
- 8.3 Electrical measurements within OEM-specified tolerance of nameplate value

7.8 Superheat deviation	_____ °F DB (Value 7.6 - Value 7.7)		
7.9 Value 7.8 is 3°F or Value 7.8 is a 5°F			
7.10 An OEM test procedure (e.g., as defined for a ground-source heat pump) has been used in place of sub-cooling or superheat process and documentation has been attached that defines the procedure			
8. Electrical Measurements – Taken at electrical disconnect while component is in operation			
8.1 Evaporator or furnace air handler fan	_____ amperage _____ line voltage		
8.2 Condenser unit	_____ amperage _____ line voltage		
8.3 Electrical measurements within OEM-specified tolerance of nameplate value			
9. Air Flow Tests			
9.1 Air volume at evaporator	_____ CFM		
9.2 Test performed in which mode?	<input type="checkbox"/> Heating <input type="checkbox"/> Cooling		
9.3 Return duct static pressure	_____ INWC Test Hole Location: _____		
9.4 Supply duct static pressure	_____ INWC Test Hole Location: _____		
9.5 Test hole locations are well-marked and accessible			
9.6 Airflow volume at evaporator (Value 9.1) at fan design speed and full operating load, a 10% of the airflow required per system design (Value 2.16) or within range recommended by OEM			
10. Air Balance			
10.1 Balancing report prepared and attached indicating the room name and design airflow for each supply and return register. In addition, final individual room airflow measured and documented through one of the following options			
10.1.1 Measured by contractor using ASHRAE 62.1-2007 protocol. Documented by contractor on the balancing report, & verified by contractor to be within the greater of a 20% or 25 CFM of design airflow. (CR)			
10.1.2 To be measured, documented, and verified by a Rater per Item 10.2 of the HVAC System QI Rater Checklist			
11. System Controls			
11.1 Operating and safety controls meet OEM requirements			
11.2 Corrosion-resistant drain pan, properly sloped to drainage system, included with each HVAC component that produces condensate			
12.1 HVAC Company Name _____ HVAC Contractor Signature _____ Credentialed Organization: ACCA / A/E / Other _____ Date _____			
12.2 Builder Name: _____ Builder Signature: _____ Date _____			

HVAC Contractor Checklist Section #9

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
 HVAC System Quality Installation Contractor Checklist

9. Air Flow Tests

9.1 Air volume at evaporator: _____ CFM

9.2 Test performed in which mode? Heating Cooling

9.3 Return duct static pressure: _____ IWC Test Hole Location: ²³ _____

9.4 Supply duct static pressure: _____ IWC Test Hole Location: ²³ _____

9.5 Test hole locations are well-marked and accessible ²³

9.6 Airflow volume at evaporator (Value 9.1), at fan design speed and full operating load, $\pm 15\%$ of the airflow required per system design (Value 2.16) or within range recommended by OEM


7.4 Subcooling deviation	_____ °F DB (Value 7.2 - Value 7.3)	<input type="checkbox"/>	<input type="checkbox"/>
For System with Fixed Orifice			
7.5 Evaporator saturation temperature	_____ °F DB (Using Value 6.5)	<input type="checkbox"/>	<input type="checkbox"/>
7.6 Superheat value	_____ °F DB (Value 6.6 - Value 7.5)	<input type="checkbox"/>	<input type="checkbox"/>
7.7 OEM superheat goal	_____ °F DB (Using superheat tables and Values 6.1 & 6.2)	<input type="checkbox"/>	<input type="checkbox"/>
7.8 Superheat deviation	_____ °F DB (Value 7.6 - Value 7.5)	<input type="checkbox"/>	<input type="checkbox"/>
7.9 Value 1.4 is $\pm 3\%$ or Value 7.8 is $\pm 5\%$		<input type="checkbox"/>	<input type="checkbox"/>
7.10 An OEM test procedure (e.g., as defined for a ground-source heat pump) has been used in place of sub-cooling or superheat process and documentation has been attached that defines this procedure		<input type="checkbox"/>	<input type="checkbox"/>
8. Electrical Measurements - Taken at electrical disconnect while component is in operation			
8.1 Compressor or fan motor handle fan	_____ amp/phase _____ line voltage	<input type="checkbox"/>	<input type="checkbox"/>
8.2 Condenser unit	_____ amp/phase _____ line voltage	<input type="checkbox"/>	<input type="checkbox"/>
8.3 Electrical measurements within OEM-specified tolerance of nameplate value		<input type="checkbox"/>	<input type="checkbox"/>
9. Air Flow Tests			
9.1 Air volume at evaporator	_____ CFM	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Test performed in which mode?	<input type="checkbox"/> Heating <input type="checkbox"/> Cooling	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Return duct static pressure	_____ IWC Test Hole Location ²³	<input type="checkbox"/>	<input type="checkbox"/>
9.4 Supply duct static pressure	_____ IWC Test Hole Location ²³	<input type="checkbox"/>	<input type="checkbox"/>
9.5 Test hole locations are well-marked and accessible ²³		<input type="checkbox"/>	<input type="checkbox"/>
9.6 Airflow volume at evaporator (Value 9.1), at fan design speed and full operating load, $\pm 15\%$ of the airflow required per system design (Value 2.16) or within range recommended by OEM		<input type="checkbox"/>	<input type="checkbox"/>
10. Air Balance			
10.1 Balancing report prepared and attached indicating the room name and design airflow for each supply and return register. In addition, final individual room airflow measured and documented through one of the following systems		<input type="checkbox"/>	<input type="checkbox"/>
10.1.1 Measured by contractor using ANSI / ACCA's Q-300 protocol, documented by contractor on the balancing report, & verified by contractor to be within the greater of 20% or 25 CFM of design airflow		<input type="checkbox"/>	<input type="checkbox"/>
10.1.2 To be measured, documented, and verified by a Rater per Item 1.4.2 of the HVAC System Qi Rater Checklist		<input type="checkbox"/>	<input type="checkbox"/>
11. System Controls			
11.1 Operating and safety controls meet OEM requirements		<input type="checkbox"/>	<input type="checkbox"/>
12. Drain pan			
12.1 Condensate-regiment drain pan, properly sloped to drainage system, included with each HVAC component that produces condensate		<input type="checkbox"/>	<input type="checkbox"/>
HVAC Company Name _____ HVAC Contractor Signature _____ Credentialing Organization: ACCA / AE / Other _____ HVAC Contractor Name _____ Builder Signature _____ Date _____			

Examples of return or supply duct static pressure measurement locations are:

- Plenum, cabinet, trunk duct, as well as front, back, left or right side
- **Test hole locations shall be well marked and accessible**



Static Pressure Measurements




External Static Pressure (EPS)

- The measurement of the resistance to the flow of air in the duct system that the furnace fan has to work against
- Everything external of the furnace cabinet
 - Resistance to flow on the Supply side:
 - AC Coil
 - Supply duct
 - Register covers
 - Resistance to flow on the Return side:
 - Filter
 - Return duct
 - return grills
- ESP is the sum of the return pressure (-) and the supply pressure (+) created by the blower




External Static Pressure (EPS)

- ESP is measured using a manometer and is expressed in inches of water column (i.e., #” WC)
- Return side readings are taken at the inlet to the furnace blower after the filter
- Supply side readings are taken as the air is exiting the furnace cabinet before the evaporator coil
- The sum of the two measurements are added together regardless of + or – signs to express the total ESP



External Static Pressure



Design Targets

Find targets in design submittal

- Static pressures
- Airflows through air handler
 - Heating
 - Cooling
- Control strategy

Cooling Equipment Summary			
Make	Carrier		
Trade	BASE 13 PURON AC		
Cond	24ABB324C30		
Coil	CNPV*2414A**		
AHRI ref no.	3040365		
Efficiency	11.7 EER, 14 SEER		
Sensible cooling	20205	Btuh	
Latent cooling	2755	Btuh	
Total cooling	22960	Btuh	
Actual air flow	1340	cfm	
Air flow factor	0.76	cfm/Btuh	
Static pressure	0.70	in H2O	
Load sensible heat ratio	1.00		



The only test done both by the Rater and the HVAC Contractor

Between the filter and the blower

Test hole locations shall be well marked and accessible



Between the cabinet and the AC Coil



9.6

- Airflow volume at evaporator (Value 9.1), at fan design speed and full operating load, $\pm 15\%$ of the airflow required per system design (Value 2.16) or within range recommended by OEM

9.1 Air volume at evaporator: _____ CFM

2.16 Design Airflow:

- Energy Star is no longer telling you how to test air flow



Flow Grid/plate: option

- The Flow grid temporarily replaces the filter in the air handler distribution system
- If the filter location is directly adjacent to the air handler, the Flow grid will measure the total air handler flow
 - i.e. flow across the heat exchanger and coil
- If the filter is located remotely at a central return, the Flow grid will measure airflow through the central return



Air Handler OEM Specs option

Blower Performance

AIR DELIVERY-CFM (WITH FILTER)* Carrier 58MCB

UNIT SIZE	RETURN-AIR SUPPLY	SPEED	EXTERNAL STATIC PRESSURE (In. wc)							
			0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8
040-08	1 side or bottom	High	1075	1040	995	945	895	840	760	670
		Med-Low	850	825	780	740	685	635	560	480
		Low	740	700	650	620	565	515	455	385
040-12	1 side or bottom	High	1470	1415	1400	1285	1215	1120	995	890
		Med-High	1315	1280	1235	1180	1115	1035	930	825
		Med-Low	1125	1110	1085	1045	990	915	830	740
060-08	1 side or bottom	High	1100	1065	1005	945	900	805	730	610
		Med-Low	890	865	810	765	705	620	540	475
		Low	745	710	670	625	565	505	425	360
060-12	1 side or bottom	High	1430	1375	1325	1275	1200	1135	1040	935
		Med-High	1270	1260	1215	1160	1105	1035	950	850
		Med-Low	1070	1055	1045	1015	975	920	850	750
060-16	1 side or bottom	High	1700	1695	1640	1580	1545	1450	1380	1310
		Med-High	1500	1465	1435	1385	1355	1300	1250	1185
		Med-Low	1325	1295	1265	1230	1190	1150	1105	1050
080-12	1 side or bottom	High	1535	1470	1405	1330	1245	1160	1065	935
		Med-High	1395	1350	1300	1225	1155	1080	985	880
		Med-Low	1200	1175	1125	1065	1030	970	890	780
080-16	1 side or bottom	High	1750	1685	1635	1575	1525	1445	1380	1310
		Med-High	1495	1455	1405	1355	1305	1250	1185	1120
		Med-Low	1310	1260	1225	1170	1125	1095	1040	980
		Low	1135	1105	1075	1040	995	995	910	860



HVAC Contractor Checklist Section #10

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist

5. Selected Furnace, if Furnace to be installed

	Min/Max	Verified	OK
5.1 Furnace Manufacturer & Model		<input type="checkbox"/>	<input type="checkbox"/>
5.2 Listed Efficiency	AFUE	<input type="checkbox"/>	<input type="checkbox"/>
5.3 Listed Output Heating Capacity	Btus	<input type="checkbox"/>	<input type="checkbox"/>
5.4 Listed Output Heat Cap. (Value 5.3) is 100-140% of Design Total Heat Loss (Value 2.15) or next control size		<input type="checkbox"/>	<input type="checkbox"/>

6. Refrigerant Tests - Run system for 15 minutes before testing
 Note: If outdoor ambient temperature at the condenser is < 50°F or, if known, below the manufacturer recommended minimum operating temperature for the cooling cycle then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6.1.

	Min/Max	Verified	OK
6.1 Outdoor ambient temperature at condenser	°F DB	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Return-side air temperature inside duct near evaporator, during cooling mode	°F DB	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Liquid line pressure	psig	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Liquid line temperature	°F DB	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Suction line pressure	psig	<input type="checkbox"/>	<input type="checkbox"/>
6.6 Suction line temperature	°F DB	<input type="checkbox"/>	<input type="checkbox"/>

7. Refrigerant Calculations

	Min/Max	Verified	OK
7.1 Condenser saturation temperature	°F DB (Using Value 6.3)	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Subcooling value	°F DB (Value 7.1 - Value 6.4)	<input type="checkbox"/>	<input type="checkbox"/>
7.3 OEM subcooling goal	°F DB	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Subcooling deviation	°F DB (Value 7.2 - Value 7.3)	<input type="checkbox"/>	<input type="checkbox"/>

For System with Fixed Orifice

	Min/Max	Verified	OK
7.5 Evaporator saturation temperature	°F DB (Using Value 6.5)	<input type="checkbox"/>	<input type="checkbox"/>
7.6 Superheat value	°F DB (Value 6.6 - Value 7.5)	<input type="checkbox"/>	<input type="checkbox"/>
7.7 OEM superheat goal	°F DB (Using superheat tables and Values 6.1 & 6.2)	<input type="checkbox"/>	<input type="checkbox"/>
7.8 Superheat deviation	°F DB (Value 7.6 - Value 7.7)	<input type="checkbox"/>	<input type="checkbox"/>
7.9 Value 7.6 is a 2°F or Value 7.8 is a 5°F		<input type="checkbox"/>	<input type="checkbox"/>

7.10 An OEM test procedure (e.g., as defined for a ground-source heat pump) has been used in place of sub-cooling or super-heat process and documentation has been attached that defines this procedure

8. Electrical Measurements - Failure of electrical disconnect while component is in operation

	Min/Max	Verified	OK
8.1 Evaporator or furnace air handler fan	amperage, line voltage	<input type="checkbox"/>	<input type="checkbox"/>
8.2 Condenser unit	amperage, line voltage	<input type="checkbox"/>	<input type="checkbox"/>
8.3 Electrical measurements within OEM-specified tolerance of nameplate value		<input type="checkbox"/>	<input type="checkbox"/>

10. Air Balance

10.1 Balancing report prepared and attached indicating the room name and design airflow for each supply and return register. In addition, final individual room airflows measured and documented through one of the following options:

10.1.1 Measured by contractor using ANSI / ACCA 5 QI-2007 protocol, documented by contractor on the balancing report, & verified by contractor to be within the greater of ± 20% or 25 CFM of design airflow ³⁴ OR;

10.1.2 To be measured, documented, and verified by a Rater per Item 1.4.2 of the HVAC System QI Rater Checklist

<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>

10.1.3 To be measured, documented, and verified by a Rater per Item 1.4.2 of the HVAC System QI Rater Checklist

11. System Controls

11.1 Operating and safety controls meet OEM requirements

12. Drain pan

12.1 Condensate-drain pan properly sloped to drainage system, included with each HVAC component that produces condensate

HVAC Company Name: _____ Credentialed Organization: ACCA / ARI / Other _____
 HVAC Contractor Name: _____ HVAC Contractor Signature: _____ Date: _____
 Builder Name: _____ Builder Signature: _____ Date: _____

Footnote: #24 Ducts shall not include coiled or looped ductwork except to the extent needed for acoustical control

- Aurora – 2 soft bends
- Balancing dampers or proper duct sizing shall be used instead of loops to limit flow to diffusers
- When balancing dampers are used, they shall be located at the trunk to limit noise **unless** the trunk will not be accessible when the balancing process is conducted

- In such cases, Opposable Blade Dampers (OBD) or dampers located in the duct boot are permitted

Balancing Report 10.2

- Includes supply and return register location
 - Room name
- Design flow
- Actual measured flow
- Altitude adjustment

Result Summary													
Total System Flow ↑	Main floor		Upper level		Total System Flow	Main		Upper					
	Static pres	CFM	Static pres	CFM		CFM	CFM	A/C tons =					
Cooling Speed	0.5 IWC	740	0.5 IWC		Cooling Speed	773			2				
Heating Speed					Heating Speed	↑	↑						
Based on Manufacturers Blower Performance Specifications													
Duct Flow Testing	All Rooms + or - 20% of design				Ahnor flow hood cfm		All Rooms < 3 pascals						
	S	R	Measured CFM	Designed CFM (Heat/Cool)	Measured CFM	% DIFFERENCE	1st Floor Rooms	S	R	Measured CFM	Designed CFM (Heat/Cool)	Measured CFM	% DIFFERENCE
UNFINISHED							PDR	S		15	21		-29%
							KITCHEN	S		57	61		-7%
							DINING	S		100	120		-17%
BASE													

Flow hoods



HVAC Contractor Checklist Section #11

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist

	Builder Verified	Contractor Verified	NA
5. Selected Furnace, if Furnace to be Installed			
5.1 Furnace Manufacturer & Model:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.2 Listed Efficiency:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.3 Listed Output Heating Capacity:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.4 Listed Output Heat Cap. (Value 5.3) is 100-140% of Design Total Heat Loss (Value 2.15) or next nominal size.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. Refrigerant Tests - Run system for 10 minutes before testing <small>Note: If outdoor ambient temperature at the condenser is 50°F or above, below the manufacturer-recommended minimum operating temperature for the cooling cycle, then the system shall include a TXV, and the contractor shall mark "NA" on the Checklist for Section 6.1.1.</small>			
6.1 Outdoor ambient temperature at condenser:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Return-side air temperature inside duct near evaporator, during cooling mode:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Liquid line pressure:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Liquid line temperature:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Suction line pressure:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.6 Suction line temperature:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. Refrigerant Calculations			
<i>For System with Thermal Expansion Valve (TXV)</i>			
7.1 Condenser saturation temperature:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Subcooling value:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 OEM subcooling goal:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Subcooling deviation:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<i>For System with Fixed Orifice</i>			
7.5 Evaporator saturation temperature:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.6 Superheat value:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.7 OEM superheat goal:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.8 Superheat deviation:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.9 Value 7.4 is 2.3°F or Value 7.8 is 4.5°F	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.10 An OEM test procedure (e.g., as defined for a ground-source heat pump) has been used in place of sub-cooling or superheat process and documentation has been attached for review per procedure.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. Electrical Measurements - Taken at electrical disconnect while component is in operation			
8.1 Evaporator or furnace air handler fan: _____ amp/phase _____ line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.2 Condenser coil: _____ amp/phase _____ line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.3 Electrical measurements within OEM-specified tolerance of nameplate value	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. Air Flow Tests			
9.1 An orifice at evaporator: _____ CFM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Test performed in which mode? <input type="checkbox"/> Heating <input type="checkbox"/> Cooling	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Return duct static pressure: _____ inWG Test Hole Location: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.4 Supply duct static pressure: _____ inWG Test Hole Location: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.5 Test hole locations are well-marked and accessible. <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.6 Airflow volume at evaporator (Value 9.1), at the design speed and full operating load, is 15% of the airflow required per system design (Value 2.16) or within range recommended by OEM.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. Air Balance			
10.1 Balancing report prepared and attached indicating the room name and design airflow for each room and return register. In addition, final individual room airflow measured and documented through one of the following options:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10.1.1 Measured by contractor using ASHRAE 154-2007 protocol, documented by contractor on the balancing report, & verified by contractor to be within the greater of a 20% or 25 CFM design airflow. <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10.1.2 To be measured, documented, and verified by a Rater per Item 11.1 of the HVAC System QR Rater Checklist.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. System Controls			
11.1 Operating and safety controls meet OEM requirements	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
12. Drain Pan			
12.1 Corrosion-resistant drain pan, properly sloped to drainage system, included with each HVAC component that produces condensate.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC Company Name: _____ Credentiating Organization: ACCA / AIE / Other			
HVAC Contractor Name: _____		HVAC Contractor Signature: _____ Date: _____	
Builder Name: _____		Builder Signature: _____ Date: _____	



11. System Controls
 11.1 Operating and safety controls meet OEM requirements



HVAC Contractor Checklist Section #12

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Contractor Checklist

5. Selected Furnace, if Furnace to be installed

	Builder	Verified	Com.	N/A
5.1 Furnace Manufacturer & Model		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.2 Listed Efficiency	AFUE	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.3 Listed Output Heating Capacity	BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.4 Listed Output Heat Cap. (Value 5.2) is 100-142% of Design Total Heat Loss (Value 2.15) or next normal size ¹¹		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6. Refrigerant Tests - Run system for 15 minutes before testing.
 Note: If outdoor ambient temperature at the condenser is < 55°F or, if frozen, below the manufacturer recommended minimum operating temperature for the cooling cycle, then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6.1.

6.1 Outdoor ambient temperature at condenser	°F DB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Return-side air temperature inside duct near evaporator, during cooling mode	°F WB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Liquid line pressure	psig	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Liquid line temperature	°F DB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Suction line pressure	psig	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.6 Suction line temperature	°F DB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

7. Refrigerant Calculations

For System with Thermal Expansion Valve (TXV)		Builder	Verified	Com.	N/A
7.1 Condenser saturation temperature	°F DB (Using Value 6.3)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Subcooling value	°F DB (Value 7.1 - Value 6.4)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 OEM subcooling goal	°F DB		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Subcooling deviation	°F DB (Value 7.2 - Value 7.3)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

For System with Fixed Orifice		Builder	Verified	Com.	N/A
7.5 Evaporator saturation temperature	°F DB (Using Value 6.5)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.6 Superheat value	°F DB (Value 6.6 - Value 7.5)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.7 OEM superheat goal	°F DB (Using superheat tables and Values 6.1 & 6.2)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.8 Superheat deviation	°F DB (Value 7.6 - Value 7.7)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.9 Value 7.4 is a 3°F or Value 7.8 is a 5°F			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.10 An OEM test procedure (e.g., as defined for a ground-source heat pump) has been used in place of sub-cooling or super-heat process and documentation has been attached that defines this procedure			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

8. Electrical Measurements - Taken at electrical disconnect while component is in operation

8.1 Evaporator fan handler fan	amperage	line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.2 Condenser unit	amperage	line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.3 Electrical measurements within OEM-specified tolerance of nameplate value			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

9. Air Flow Tests

9.1 Air volume at evaporator	CFM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Test performed in which mode?	<input type="checkbox"/> Heating <input type="checkbox"/> Cooling	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Return duct static pressure	inWC	Test Hole Location ¹²	<input type="checkbox"/>	<input type="checkbox"/>
9.4 Supply duct static pressure	inWC	Test Hole Location ¹²	<input type="checkbox"/>	<input type="checkbox"/>
9.5 Test hole locations are well-sealed and accessible ¹³			<input type="checkbox"/>	<input type="checkbox"/>
9.6 Air volume at evaporator (Value 9.1), at fan design speed and full operating load, is 15% of the airflow required per system design (Value 2.15) or within range recommended by OEM			<input type="checkbox"/>	<input type="checkbox"/>

10. Air Balance

10.1 Balancing report prepared and attached indicating the room name and design airflow for each supply and return register. In addition, final individual room airflow measured and documented (one of the following values)

12. Drain pan

12.1 Corrosion-resistant drain pan, properly sloped to drainage system, included with each HVAC component that produces condensate

condensate ¹⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	--------------------------	--------------------------

HVAC Company Name: _____
 HVAC Contractor Name: _____ HVAC Contractor Signature: _____ Date: _____
 Builder Name: _____ Builder Signature: _____ Date: _____

Footnote: 25

- Condensate pan shall be made of corrosion-resistant materials
 - Galvanized steel / plastic
- Drain pan shall drain condensate to a conspicuous point of disposal to alert occupants in the event of a stoppage of the primary drainage system
- And shall be equipped with a backflow prevention valve when drained to a shared drainage system, such as a storm water management system

Signature

ENERGY STAR Qualified Homes, Version 3 (Rev. 05)
HVAC System Quality Installation Contractor Checklist

5. Selected Furnace, if Furnace to be installed

	Builder	Verified	Com.	N/A
5.1 Furnace Manufacturer & Model		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.2 Furnace Serial #		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.3 Listed Efficiency	AFUE	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.4 Listed Output Heating Capacity	BTU/h	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.5 Listed Output Heat Cap. (Value 5.4) is 100-142% of Design Total Heat Loss (Value 2.15) or next normal size ¹¹		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6. Refrigerant Tests - Run system for 15 minutes before testing.
 Note: If outdoor ambient temperature at the condenser is < 55°F or, if frozen, below the manufacturer recommended minimum operating temperature for the cooling cycle, then the system shall include a TXV, and the contractor shall mark "N/A" on the Checklist for Section 6.1.

6.1 Outdoor ambient temperature at condenser	°F DB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Return-side air temperature inside duct near evaporator, during cooling mode	°F WB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Liquid line pressure	psig	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Liquid line temperature	°F DB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Suction line pressure	psig	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.6 Suction line temperature	°F DB	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

7. Refrigerant Calculations

For System with Thermal Expansion Valve (TXV)		Builder	Verified	Com.	N/A
7.1 Condenser saturation temperature	°F DB (Using Value 6.3)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Subcooling value	°F DB (Value 7.1 - Value 6.4)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 OEM subcooling goal	°F DB		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Subcooling deviation	°F DB (Value 7.2 - Value 7.3)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

For System with Fixed Orifice		Builder	Verified	Com.	N/A
7.5 Evaporator saturation temperature	°F DB (Using Value 6.5)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.6 Superheat value	°F DB (Value 6.6 - Value 7.5)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.7 OEM superheat goal	°F DB (Using superheat tables and Values 6.1 & 6.2)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.8 Superheat deviation	°F DB (Value 7.6 - Value 7.7)		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.9 Value 7.4 is a 3°F or Value 7.8 is a 5°F			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.10 An OEM test procedure (e.g., as defined for a ground-source heat pump) has been used in place of sub-cooling or super-heat process and documentation has been attached that defines this procedure			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

8. Electrical Measurements - Taken at electrical disconnect while component is in operation

8.1 Evaporator fan handler fan	amperage	line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.2 Condenser unit	amperage	line voltage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.3 Electrical measurements within OEM-specified tolerance of nameplate value			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

9. Air Flow Tests

9.1 Air volume at evaporator	CFM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Test performed in which mode?	<input type="checkbox"/> Heating <input type="checkbox"/> Cooling	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Return duct static pressure	inWC	Test Hole Location ¹²	<input type="checkbox"/>	<input type="checkbox"/>
9.4 Supply duct static pressure	inWC	Test Hole Location ¹²	<input type="checkbox"/>	<input type="checkbox"/>
9.5 Test hole locations are well-sealed and accessible ¹³			<input type="checkbox"/>	<input type="checkbox"/>
9.6 Air volume at evaporator (Value 9.1), at fan design speed and full operating load, is 15% of the airflow required per system design (Value 2.15) or within range recommended by OEM			<input type="checkbox"/>	<input type="checkbox"/>

10. Air Balance

10.1 Balancing report prepared and attached indicating the room name and design airflow for each supply and return register. In addition, final individual room airflow measured and documented (one of the following values)

12. Drain pan

12.1 Corrosion-resistant drain pan, properly sloped to drainage system, included with each HVAC component that produces condensate


condensate ¹⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
--------------------------	--------------------------	--------------------------	--------------------------

HVAC Company Name: _____
 HVAC Contractor Name: _____ HVAC Contractor Signature: _____ Date: _____
 Builder Name: _____ Builder Signature: _____ Date: _____

- New
- A line has been added to the signature block For contractors to indicate their credentialing organization

Credentialing Organization: ACCA / AE / Other

HVAC Rater's Checklist



ENERGY STAR® CERTIFIED NEW HOME

Builder Name: KB Home
Permit Date/Number:
Home Address: 10931 E 29th Pl
Denver, CO 80238

Rating Company: EnerzyLogic, Inc
Rater Identification Number: 9124083
Rating Date: 7/29/2013
Version: 3.0

Standard Features of an ENERGY STAR Certified New Home
Your ENERGY STAR certified new home has been designed, constructed, and independently verified to meet rigorous requirements for energy efficiency set by the U.S. Environmental Protection Agency (EPA), including:

Thermal Enclosure System
A complete thermal enclosure system that includes comprehensive air sealing, quality-installed insulation and high-performing windows to deliver improved comfort and lower utility bills.

Air Infiltration Test: **Htg: 919 Cfg: 919 CFM50**

Primary Insulation Levels:
Ceiling: R-38, R-w/E; Frost/Att: R-11.8; Slat: R-6.6
ADWd: R-20.0; Floor: R-50.4
Primary Window Efficiency:
U-Value: 0.340, SHGC: 0.329

Water Management System
A comprehensive water management system to protect roofs, walls, and foundations.

Flashing, a drainage plane, and site grading to move water from the roof to the ground and then away from the home.

Water-resistant materials on below-grade walls and underneath slabs to reduce the potential for water entering into the home.

Management of moisture levels in building materials during construction.

Heating, Cooling, and Ventilation System
A high-efficiency heating, cooling system, and ventilation system that is designed and installed for optimal performance.

Total Duct Leakage:
79.8 CFM @ 25 Pascals

Duct Leakage to Outdoors:
6.96 CFM @ 25 Pascals

Primary Heating (System Type • Fuel Type • Efficiency):
Fuel-fired air distribution, Natural gas, 92.1 AFUE.


Primary Cooling (System Type • Fuel Type • Efficiency):
Air conditioner, Electric, 13.0 SEER.

Energy Efficient Lighting and Appliances
Energy efficient products to help reduce utility bills, while providing high-quality performance.


ENERGY STAR Qualified Lighting: 100%

ENERGY STAR Qualified Appliances and Fans:
Refrigerators: 0; Dishwashers: 0
Ceiling Fans: 0; Exhaust Fans: 0

Primary Water Heater (System Type • Fuel Type • Efficiency):
Conventional, Natural gas, 6.79 EF, 68.9 O.G.



HERS® Index



ENERGY STAR Certified Homes, Version 3 (Rev. 07)

HVAC System Quality Installation Rater Checklist ¹

Home Address: _____ City: _____ State: _____ Zip Code: _____

1. Review of HVAC System Quality Installation Contractor Checklist ²	Must Correct	Rater Verified	N/A
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.1B), and AHRI certificate (3.13).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist Item # indicated in parenthesis): ³			
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location ⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 Home orientation (2.5) matches orientation of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

- Checklist designed to align with ASHRAE 62.2 & ANSI/ACCA's 5 QI 2007 Protocol
- **The Rater is only responsible for ensuring** that the Contractor has **completed** the Contractor Checklist **in its entirety** and **verifying** the discrete objective parameters referenced in **Section 1 of this Checklist**
- The Rater is not responsible for assessing the accuracy of the load calculations or field verifications included or for verifying the accuracy of every input on the Contractor Checklist

Raters are required to review the following

1. Review of HVAC System Quality Installation Contractor Checklist ²	Must Correct	Rater Verified	N/A
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), and AHRI certificate (3.13).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist Item # indicated in parenthesis): ³			
1.2.1 <u>Outdoor design temperatures</u> (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location ⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 <u>Home orientation</u> (2.5) matches orientation of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.3 Number of occupants (2.6) equals number of occupants in rated home ⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.4 <u>Conditioned floor area</u> (2.7) is within $\pm 10\%$ of conditioned floor area of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.5 <u>Window area</u> (2.8) is within $\pm 10\%$ of calculated window area of rated home	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.6 <u>Predominant window SHGC</u> (2.9) is within 0.1 of predominant value in rated home ⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.7 Listed latent cooling capacity (3.8) exceeds design latent heat gain (2.12)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size ⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 5.1), and AHRI certificate or OEM catalog data all match ⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (as determined using pressure / temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees) ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) value is within ± 3 °F of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within ± 5 °F of the reported target temperature (7.7). ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Rater-verified supply & return duct static pressure $\leq 110\%$ of contractor values (9.3, 9.4)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4 <u>Contractor-prepared balancing report</u> indicating the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflows measured and documented on balancing report through one of the following options:			
1.4.1 Measured and documented by contractor (10.1.1), OR;	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.2 Measured by Rater using Section 804.2 of the Mortgage Industry National HERS Standard, documented by Rater & verified by Rater to be within the greater of $\pm 20\%$ or 25 CFM of design airflow (10.1.2)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 HVAC contractor holds credentials necessary to complete the HVAC System QI Contractor Checklist ¹⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

- 1.2.7 Listed latent cooling capacity (3.8) exceeds design latent heat gain (2.12)
- 1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13)

Section 2 HVAC Contractor Checklist Heating and Cooling Design

2.12 Design Latent Heat Gain:	0
2.13 Design Sensible Heat Gain:	16376
2.14 Design Total Heat Gain:	16376
2.15 Design Total Heat Loss:	34274
2.16 Design Airflow: ¹³	740
2.17 Design Duct Static Pressure: ¹⁴	.8

Section 3 HVAC Contractor Checklist: Cooling Equipment

3.8 Listed Sys. Latent Capacity at Design Cond.: ¹⁸	3860	BTUh
3.9 Listed Sys. Sensible Capacity at Design Cond.: ¹⁸	19140	BTUh
3.10 Listed Sys. Total Capacity at Design Cond.: ¹⁸	23000	BTUh

- 1.2.7 --- (3.8) 3860 > (2.12) 0 = Pass
- 1.2.8 --- (3.9) 19140 > (2.13) 16376 = Pass



1.2.9 Listed total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size

Section 2 HVAC Contractor Checklist Heating and Cooling Design

2.12 Design Latent Heat Gain:	0
2.13 Design Sensible Heat Gain:	16376
2.14 Design Total Heat Gain:	16376
2.15 Design Total Heat Loss:	34274
2.16 Design Airflow: ¹³	740
2.17 Design Duct Static Pressure: ¹⁴	.8

Section 3 HVAC Contractor Checklist: Cooling Equipment

3.8 Listed Sys. Latent Capacity at Design Cond.: ¹⁸	3860	BTUh
3.9 Listed Sys. Sensible Capacity at Design Cond.: ¹⁸	19140	BTUh
3.10 Listed Sys. Total Capacity at Design Cond.: ¹⁸	23000	BTUh

- (3.10) 23000 (2.14) 16376

16376 x 1.15 = 18832.4 Next nominal size 24000



Footnote #7

1.2.9 Listed total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size ⁷

- For cooling systems, the next largest nominal piece of equipment may be used that is available to satisfy the **latent and sensible** requirements.
- Single-speed systems generally have OEM nominal size increments of ½ ton. Multi-speed or multi-stage equipment may have OEM nominal size increments of one ton. Therefore, the use of these advanced system types can provide extra flexibility to meet the equipment sizing requirements.



1. Review of HVAC System Quality Installation Contractor Checklist ²	Must Correct	Rater Verified	N/A
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), and AHRI certificate (3.13).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Footnote #8			
<ul style="list-style-type: none"> In cases where the condenser unit is installed after the time of inspection: <ul style="list-style-type: none"> The HVAC manufacturer and model numbers on installed equipment can be documented through the use of photographs provided by the HVAC Contractor after installation is complete 			
1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size ⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 5.1), and AHRI certificate or OEM catalog data all match ⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (as determined using pressure / temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees) ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) value is within ± 3 °F of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within ± 5 °F of the reported target temperature (7.7). ³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Rater-verified supply & return duct static pressure $\leq 110\%$ of contractor values (9.3, 9.4)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4 Contractor-prepared balancing report indicating the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflows measured and documented on balancing report through one of the following options:			
1.4.1 Measured and documented by contractor (10.1.1), OR;	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.2 Measured by Rater using Section 804.2 of the Mortgage Industry National HERS Standard, documented by Rater, & verified by Rater to be within the greater of $\pm 20\%$ or 25 CFM of design airflow (10.1.2)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 HVAC contractor holds credentials necessary to complete the HVAC System QI Contractor Checklist ¹⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (as determined using pressure / temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees)

Section 6: Refrigerant Tests

- 6.1 Outdoor ambient temperature at condenser: 85 °F DB
- 6.2 Return-side air temperature inside duct near evaporator, during cooling mode: 75 °F WB
- 6.3 Liquid line pressure: 350 psig
- 6.4 Liquid line temperature: 100 °F DB
- 6.5 Suction line pressure: 130 psig
- 6.6 Suction line temperature: 52 °F DB

Section 7; Refrigerant Calculation

For System with Thermal Expansion Valve (TXV):

- 7.1 Condenser saturation temperature: 107 °F DB (Using Value 6.3)
- 7.2 Subcooling value: 7 °F DB (Value 7.1 - Value 6.4)
- 7.3 OEM subcooling goal: 10 °F DB
- 7.4 Subcooling deviation: 3 °F DB (Value 7.2 – Value 7.3)

▪ (6.3) 350 (7.1) 107

Sat Temp (°F)	R-22	R-407C Liquid Pressure	R-407C Vapor Pressure	R-410A Liquid Pressure	R-11	R-123
100	198.4	224.1	194.6	318.9	11.3	8.6
<u>105</u>	213.2	241.0	210.3	<u>342.4</u>	13.4	10.6
110	228.8	258.9	226.9	367.1	15.7	12.8

HVAC Rater's Checklist

1. Review of HVAC System Quality Installation Contractor Checklist²

1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), AHRI certificate (3.15), and balancing report (10.2).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Footnote #9			
<ul style="list-style-type: none"> If contractor has indicated that an OEM test procedure has been used in place of a sub-cooling or super-heat process and documentation has been attached that defines this procedure, then the box for "N/A" shall be checked for this Item 			
1.2.8 Listed sensible cooling capacity (3.11) exceeds design sensible heat gain (2.13)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.12) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size ⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.3, 5.1), and AHRI certificate or OEM catalog data all match ⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temp. (as determined using pressure / temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees) ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) or superheat (6.6 minus 7.5) value equals reported target subcooling (7.3) or superheat (7.7) temperature ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Rater-verified supply & return duct static pressure ≤ 110% of contractor values (9.3, 9.4)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

1.2.12 Calculated **subcooling** (7.1 minus 6.4) value is **within ±3** °F of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within ±5 °F of the reported target temperature (7.7). 9

Section 6: Refrigerant Tests

6.1 Outdoor ambient temperature at condenser: 85 °F DB
 6.2 Return-side air temperature inside duct near evaporator, during cooling mode: 75 °F WB
 6.3 Liquid line pressure: 350 psig
 6.4 Liquid line temperature: 100 °F DB
 6.5 Suction line pressure: 135 psig
 6.6 Suction line temperature: 52 °F DB

Section 7; Refrigerant Calculation


For System with Thermal Expansion Valve (TXV):
 7.1 Condenser saturation temperature: 107 °F DB (Using Value 6.3)
 7.2 Subcooling value: 7 °F DB (Value 7.1 - Value 6.4)
 7.3 OEM subcooling goal: 10 °F DB
 7.4 Subcooling deviation: 3 °F DB (Value 7.2 - Value 7.3)

$$(7.1) 107 - (6.4) 100 = 7^\circ$$

Footnote #9:

If contractor has indicated that an OEM test procedure has been used in place of a sub-cooling or super-heat process and documentation has been attached that defines this procedure, then the box for "N/A" shall be checked for this Item.





HVAC System Quality Installation Rater Checklist

- Duct quality installation
- Duct insulation
- Duct leakage



ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist¹

Home Address	City	Date	Eq. Code	Must Correct	Rater Verifying	N/A
1. Review of HVAC System Quality Installation Contractor Checklist¹						
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.10), and AHRI certificate (3.13).						
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist Item # indicated in parenthesis): ²						
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location. ³				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 Home orientation (2.5) matches orientation of rated home.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.3 Number of occupants (2.6) equals number of occupants in rated home. ⁴				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.4 Conditioned floor area (2.7) is within ±10% of conditioned floor area of rated home.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.5 Window area (2.8) is within ±10% of calculated window area of rated home.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.6 Predominant window SHGC (2.9) is within 0.1 of predominant value in rated home. ⁵				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.7 Listed latent cooling capacity (3.8) exceeds design latent heat gain (2.12).				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13).				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or meet nominal size. ⁶				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 5.1), and AHRI certificate or OEM catalog data all match. ⁷				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (see determined using pressure / temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.2) saturation temperature ± 3 degrees. ⁸				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (1.1 minus 6.4) value is within ±3 °F of the reported target temperature (7.3), or calculated superheat (6.6 minus 7.5) value is within ±3 °F of the reported target temperature (7.7). ⁹				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Water-cooled supply & return duct static pressure ≤ 1.10% of contractor values (i.e., 0.4). ¹⁰				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4 Contractor prepared balancing report indicating the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflow measured and documented on balancing report through one of the following options:						
1.4.1 Measured and documented by contractor (10.1.1), OR:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.2 Measured by Rater using Section 804.2 of the Mortgage Industry National HERs Standard, documented by Rater, & verified by Rater to be within the greater of a 20% or 25 CFM of design airflow (10.1.2).				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 HVAC contractor holds credentials necessary to complete the HVAC System QI Contractor Checklist. ¹¹						
2. Duct Quality Installation - Applies to All Heating, Cooling, Ventilation, Exhaust, and Pressure Balancing Ducts¹²						
2.1 Connections and routing of ductwork completed without kinks or sharp bends. ¹³				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.2 No excessive coiled or looped flexible ductwork. ¹⁴				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.3 Flexible ducts in unconditioned space not installed in cavities smaller than outer duct diameter, in conditioned space not installed in cavities smaller than inner duct diameter.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.4 Flexible ducts supported at intervals as recommended by mfr, but at a distance ≤ 5 ft.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.5 Building cavities not used as supply or return ducts unless they meet Items 3.2, 3.3, 4.1, and 4.2 of this Checklist.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.6 HVAC ducts, cavities, crevices, ducts, and connections inside and outside may pass perpendicularly through exterior walls but shall not be run within exterior walls unless at least R-6 continuous insulation is provided on exterior side of the cavity, along with an interior and exterior air barrier where required by the Thermal Enclosure System Rater Checklist.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.7 Quantity & location of supply and return duct terminals match contractor balancing report. ¹⁵				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.8 Bedroom pressure balanced using any combination of transfer grille, jump ducts, dedicated return ducts, and/or undercut doors to either: a) provide 1 sq. in. of free area opening per 1 CFM of supply air, as reported on the contractor provided balancing report; or b) achieve a Rater-measured pressure differential ≤ 3 Pa with respect to the main body of the house when all bedroom doors are closed and all air handlers are operating.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3. Duct Insulation - Applies to All Heating, Cooling, Supply, Ventilation, and Pressure Balancing Ducts¹⁶						
3.1 All connections to both ducts in unconditioned spaces are insulated.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.2 Prescriptive Path: Supply ducts in unconditioned attic have insulation ≥ R-6.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.2 Performance Path: Supply ducts in unconditioned attic have insulation ≥ R-6.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.3 All other supply ducts and all return ducts in unconditioned space have insulation ≥ R-6.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

HVAC Rater's Checklist

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

Home Address	City	State	Zip Code	Must Correct	Rater Verified	NA
1. Review of HVAC System Quality Installation Contractor Checklist ¹						
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), and AHRI certificate (3.13).						
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist item # indicated in parenthesis):						
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location.				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 Home orientation (2.5) matches orientation of rated home				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.3 Number of occupants (2.8) equals number of occupants in rated home ¹				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.4 Conditioned floor area (2.7) is within ±10% of conditioned floor area of rated home				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.5 Window area (2.8) is within ±10% of calculated window area of rated home				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.6 Predominant window SHGC (2.9) is within 0.1 of predominant value in rated home ¹				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.7 Listed latent cooling capacity (3.8) exceeds design latent heat gain (2.12)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.10) is 95-119% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 5.1), and AHRI certificate or OEM catalog data all match				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (as determined using pressure/temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) value is within ±3 °F of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within ±3 °F of the reported target temperature (7.7) ¹				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. Duct Quality Installation - Applies to All Heating, Cooling, Ventilation, Exhaust, and Pressure Balancing Ducts ¹¹						
2.1 Connections and routing of ductwork completed without kinks or sharp bends. ¹²						
2.2 No excessive coiled or looped flexible ductwork. ¹³						
2.3 Flexible ducts in unconditioned space not installed in cavities smaller than outer duct diameter; in conditioned space not installed in cavities smaller than inner duct diameter						
2.4 Flexible ducts supported at intervals as recommended by mfr. but at a distance ≤ 5 ft.						
2.5 Building cavities not used as supply or return ducts unless they meet Items 3.2, 3.3, 4.1, and 4.2 of this Checklist.						
2.6 HVAC ducts, cavities used as ducts, and combustion inlets and outlets may pass perpendicularly through exterior walls but shall not be run within exterior walls unless at least R-6 continuous insulation is provided on exterior side of the cavity, along with an interior and exterior air barrier where required by the Thermal Enclosure System Rater Checklist.						
2.7 Quantity & location of supply and return duct terminals match contractor balancing report. ¹¹						
2.8 Bedrooms pressure-balanced using any combination of transfer grills, jump ducts, dedicated return ducts, and / or undercut doors to either: a) provide 1 sq. in. of free area opening per 1 CFM of supply air, as reported on the						

Footnote #11

- Items 2.7 and 2.8 do not apply to ventilation ducts
- However duct sealing does apply to ventilation and transfer ducts

HVAC Rater's Checklist Section #2


ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

Home Address	City	State	Zip Code	Must Correct	Rater Verified	NA
1. Review of HVAC System Quality Installation Contractor Checklist ¹						
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), and AHRI certificate (3.13).						
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist item # indicated in parenthesis):						
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual J design temperatures for contractor-designated design location				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 Home orientation (2.5) matches orientation of rated home				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.3 Number of occupants (2.8) equals number of occupants in rated home ¹				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.4 Conditioned floor area (2.7) is within ±10% of conditioned floor area of rated home				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.5 Window area (2.8) is within ±10% of calculated window area of rated home				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.6 Predominant window SHGC (2.9) is within 0.1 of predominant value in rated home ¹				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.7 Listed latent cooling capacity (3.8) exceeds design latent heat gain (2.12)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.8 Listed sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Listed total cooling capacity (3.10) is 95-119% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 5.1), and AHRI certificate or OEM catalog data all match				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported liquid line (6.3) or suction line (6.5) pressure, corresponding temperature (as determined using pressure/temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.5) saturation temperature (± 3 degrees)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) value is within ±3 °F of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within ±3 °F of the reported target temperature (7.7) ¹				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Rater-verified supply & return flow rates pressure ± 1.0% or operator value (3.4, 3.4)						
1.4 Contractor-prepared balancing report indicating the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflow measured and documented on balancing report through one of the following options:						
1.4.1 Measured and documented by contractor (10.1.1) OR:						
1.4.2 Measured by Rater using Section 804.2 of the Mortgage Industry National HERS Standard; documented by Rater. & verified by Rater to be within the greater of a 20% or 25 CFM of design airflow (10.1.2)						
2. Duct Quality Installation - Applies to All Heating, Cooling, Ventilation, Exhaust, and Pressure Balancing Ducts ¹¹						
2.1 Connections and routing of ductwork completed without kinks or sharp bends. ¹²						
2.2 No excessive coiled or looped flexible ductwork. ¹³						
2.3 Flexible ducts in unconditioned space not installed in cavities smaller than outer duct diameter; in conditioned space not installed in cavities smaller than inner duct diameter						
2.4 Flexible ducts supported at intervals as recommended by mfr. but at a distance ≤ 5 ft.						
2.5 Building cavities not used as supply or return ducts unless they meet Items 3.2, 3.3, 4.1, and 4.2 of this Checklist.						
2.6 HVAC ducts, cavities used as ducts, and combustion inlets and outlets may pass perpendicularly through exterior walls but shall not be run within exterior walls unless at least R-6 continuous insulation is provided on exterior side						

Footnote #12

- Kinks are to be avoided and are caused when ducts are bent across sharp corners such as framing members
- Sharp bends are to be avoided and occur when the radius of the turn in the duct is less than one duct diameter

Looking for better performance



HVAC Rater's Checklist Section #2

Footnote #12


- No coiled or looped ductwork except where needed for acoustical control
- Balancing dampers or proper duct sizing used instead of loops to limit flow
- Balancing dampers used shall be located at the trunk to limit noise unless the trunk will not be accessible when the balancing is conducted
- In such cases, Opposable Blade Dampers (OBD) or dampers that are located in the duct boot are permitted

ENERGY STAR Certified Homes, Version 3 (Rev. 07) HVAC System Quality Installation Rater Checklist ¹		Zip Code	Must Current	Rater Verified
1. Review of HVAC System Quality Installation Contractor Checklist ¹				
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), and AHRI certificate (3.13).				
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist Item # indicated in parenthesis).				
1.2.1	Outdoor design temperatures (2.8) are equal to the 1% and 99% ACCA Manual 2 design temperatures for contractor-designated design location.		<input type="checkbox"/>	<input type="checkbox"/>
1.2.2	Home orientation (2.5) matches orientation of rated home.		<input type="checkbox"/>	<input type="checkbox"/>
1.2.3	Number of occupants (2.6) equals number of occupants in rated home ¹ .		<input type="checkbox"/>	<input type="checkbox"/>
1.2.4	Conditioned floor area (2.7) is within ±10% of conditioned floor area of rated home.		<input type="checkbox"/>	<input type="checkbox"/>
1.2.5	Window area (2.8) is within ±10% of calculated window area of rated home.		<input type="checkbox"/>	<input type="checkbox"/>
1.2.6	Predominant window SHGC (2.9) is within 0.1 of predominant value in rated home ¹ .		<input type="checkbox"/>	<input type="checkbox"/>
1.2.7	Linked latent cooling capacity (3.8) exceeds design latent heat gain (2.12).		<input type="checkbox"/>	<input type="checkbox"/>
1.2.8	Linked sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13).		<input type="checkbox"/>	<input type="checkbox"/>
1.2.9	Linked total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size.		<input type="checkbox"/>	<input type="checkbox"/>
1.2.10	HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 4.1), and AHRI certificate or OEM catalog data all match.		<input type="checkbox"/>	<input type="checkbox"/>
1.2.11	Using reported liquid line (5.3) and suction line (5.5) pressure, corresponding temperature (as determined using pressure/temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.2) saturation temperature (± 2 degrees).		<input type="checkbox"/>	<input type="checkbox"/>
1.2.12	Calculated subcooling ((7.1 minus 6.4) value is within ±3 °F of the reported target temperature (7.3) or calculated superheat ((6.6 minus 7.5) value is within ±3 °F of the reported target temperature (7.7)). ¹		<input type="checkbox"/>	<input type="checkbox"/>
1.3	Water-vented supply & return duct static pressure is ±10% of contractor value (e.g., 0.4). ¹	U	U	U
1.4 Contractor-prepared balancing report indicating the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflow measured and documented on balancing report through one of the following options:				
1.4.1	Measured and documented by contractor (10.1.1). OR:		<input type="checkbox"/>	<input type="checkbox"/>
1.4.2	Measured by Rater using Section 804.2 of the Mortgage Industry National HERS Standard, documented by Rater. & verified by Rater to be within the greater of a 20% or 25 CFM of design airflow (10.1.2).		<input type="checkbox"/>	<input type="checkbox"/>
1.5 HVAC contractor holds credentials necessary to complete the HVAC System QI Contractor Checklist. ¹²				
2. Duct Quality Installation - Applies to All Heating, Cooling, Ventilation, Exhaust, and Pressure Balancing Ducts ¹³				
2.1	Connections and routing of ductwork completed without kinks or sharp bends. ¹²		<input type="checkbox"/>	<input type="checkbox"/>
2.2	No excessive coiled or looped flexible ductwork. ¹³		<input type="checkbox"/>	<input type="checkbox"/>
2.3	Flexible ducts in unconditioned space not installed in cavities smaller than outer duct diameter, in conditioned space not installed in cavities smaller than inner duct diameter.		<input type="checkbox"/>	<input type="checkbox"/>
2.4	Flexible ducts supported at intervals as recommended by mfr. but at a distance ≥ 5 ft.		<input type="checkbox"/>	<input type="checkbox"/>
2.5	Building cavities not used as supply or return ducts unless they meet Items 3.2, 3.3, 4.1, and 4.2 of this Checklist.		<input type="checkbox"/>	<input type="checkbox"/>
2.6	HVAC supply, return, exhaust, and combustion vents and outlets may pass perpendicularly through exterior walls but shall not be run within exterior walls unless at least R-4 continuous insulation is provided on exterior side of the cavity, along with an interior and exterior air barrier where required by the Thermal Enclosure System Rater Checklist. ¹⁴		<input type="checkbox"/>	<input type="checkbox"/>
2.7	Quantity & location of supply and return duct terminals match contractor balancing report. ¹⁵		<input type="checkbox"/>	<input type="checkbox"/>

2. Duct Quality Installation - Applies to All Heating, Cooling, Ventilation, Exhaust, and Pressure Balancing Ducts¹³

2.1 Connections and routing of ductwork completed without kinks or sharp bends.¹²

2.2 No excessive coiled or looped flexible ductwork.¹³



2.6 HVAC ducts, **cavities used as ducts**, and combustion inlets and outlets may pass perpendicularly through exterior walls but **shall not be run within exterior walls unless** at least R-6 continuous insulation is provided on exterior side of the cavity, along with an interior and exterior air barrier where required by the Thermal Enclosure System Rater Checklist.

- Either inside or outside of the buildings thermal envelope
 - Can't be in the middle of it unless you can achieve the needed R-value for the assembly



EnergyLogic will continue to require $\geq R-10$ to the outside

HVAC Rater's Checklist Section #2



ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist¹

Home Address:	City:	State:	Zip Code:	Rater:	Date:
1. Review of HVAC System Quality Installation Contractor Checklist¹					
1.1 HVAC System Quality Installation Contractor Checklist completed in its entirety and collected for records, along with documentation on ventilation system (1.3), full load calculations (2.18), and AHRI certificate (3.13).				<input type="checkbox"/>	<input type="checkbox"/>
1.2 Review the following parameters related to system cooling design, selection, and installation from the HVAC Contractor Checklist (Contractor Checklist item # indicated in parenthesis).					
1.2.1 Outdoor design temperatures (2.4) are equal to the 1% and 99% ACCA Manual 2 design temperatures for contractor-designated design location.				<input type="checkbox"/>	<input type="checkbox"/>
1.2.2 Home orientation (2.5) matches orientation of rated home.				<input type="checkbox"/>	<input type="checkbox"/>
1.2.3 Number of occupants (2.6) equals number of occupants in rated home ¹ .				<input type="checkbox"/>	<input type="checkbox"/>
1.2.4 Conditioned floor area (2.7) is within $\pm 10\%$ of conditioned floor area of rated home.				<input type="checkbox"/>	<input type="checkbox"/>
1.2.5 Window area (2.8) is within $\pm 10\%$ of calculated window area of rated home.				<input type="checkbox"/>	<input type="checkbox"/>
1.2.6 Predominant window SHGC (2.9) is within 0.1 of predominant value in rated home ¹ .				<input type="checkbox"/>	<input type="checkbox"/>
1.2.7 Linked latent cooling capacity (3.8) exceeds design latent heat gain (2.12).				<input type="checkbox"/>	<input type="checkbox"/>
1.2.8 Linked sensible cooling capacity (3.9) exceeds design sensible heat gain (2.13).				<input type="checkbox"/>	<input type="checkbox"/>
1.2.9 Linked total cooling capacity (3.10) is 95-115% (or 95-125% for Heat Pumps in Climate Zones 4-8) of design total heat gain (2.14), or next nominal size.				<input type="checkbox"/>	<input type="checkbox"/>
1.2.10 HVAC manufacturer and model numbers on installed equipment, Contractor Checklist (3.1, 3.2, 4.1), and AHRI certificate or OEM catalog data all match.				<input type="checkbox"/>	<input type="checkbox"/>
1.2.11 Using reported load size (4.3) or section size (4.5) pressure, corresponding temperature (as determined using pressure/temperature chart for refrigerant type) matches reported condenser (7.1) or evaporator (7.2) saturation temperature ± 2 degrees.				<input type="checkbox"/>	<input type="checkbox"/>
1.2.12 Calculated subcooling (7.1 minus 6.4) value is within $\pm 3^\circ F$ of the reported target temperature (7.3) or calculated superheat (6.6 minus 7.5) value is within $\pm 3^\circ F$ of the reported target temperature (7.7). ¹				<input type="checkbox"/>	<input type="checkbox"/>
1.3 Water-vented supply & return duct static pressure is ≤ 1.17 in. or operator value (e.g., 3.4).				<input type="checkbox"/>	<input type="checkbox"/>
1.4 Contractor-prepared balancing report indicating the room name and design airflow for each supply and return register collected by Rater for records. In addition, final individual room airflow measured and documented on balancing report through one of the following options:				<input type="checkbox"/>	<input type="checkbox"/>
1.4.1 Measured and documented by contractor (10.1.1), OR:				<input type="checkbox"/>	<input type="checkbox"/>
1.4.2 Measured by Rater using Section 804.2 of the Mortgage Industry National HERS Standard, documented by				<input type="checkbox"/>	<input type="checkbox"/>

Footnote #14

- For HVAC system with multi-speed fans, the highest design fan speed shall be used when verifying this requirement.
- Ventilation and Transfer duct work is required to be sealed with Mastic per Footnote 16 and all associated duct boots are sealed to floor, wall, or ceiling using caulk, foam, or mastic tape

2.8 Bedrooms pressure-balanced using any combination of transfer grills, jump ducts, dedicated return ducts, and / or undercut doors to either: a) provide 1 sq. in. of free area opening per 1 CFM of supply air, as reported on the contractor-provided balancing report; or b) achieve a Rater-measured pressure differential ≤ 3 Pa with respect to the main body of the house when all bedroom doors are closed and all air handlers are operating. ¹⁴

HVAC Rater's Checklist Section #3

Footnote #15

- EPA recommends (not require) that all metal ductwork not covered by Section 3 (e.g., exhaust ducts, duct boots, ducts in conditioned space) also be insulated and that insulation be sealed to duct boots to prevent condensation.



3. Duct Insulation - Applies to All Heating, Cooling, Supply Ventilation, and Pressure Balancing Ducts ¹⁵

- 3.1 All connections to trunk ducts in unconditioned space are insulated.
- 3.2 **Prescriptive Path:** Supply ducts in unconditioned attic have insulation \geq R-8.
Performance Path: Supply ducts in unconditioned attic have insulation \geq R-6.
- 3.3 All other supply ducts and all return ducts in unconditioned space have insulation \geq R-6.



HVAC Rater's Checklist Section #4

Footnote #16

- Duct leakage shall be determined and documented by a Rater using a RESNET-approved testing protocol only after all components of the system have been installed (e.g., air handler and register grilles)
- Leakage limits shall be assessed on a per-system, rather than per-home, basis

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

Item	Must Comply	Rater Verified	Pass
4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts			
4.1 Total Rater-measured duct leakage meets one of the following two options: ¹⁶			
4.1.1 Rough-in: \leq 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface, Rater-verified at final. ¹⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.1.2 Final: \leq 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register grilles atop the finished surface (e.g., drywall, flooring) installed. ¹⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors \leq 4 CFM25 per 100 sq. ft. of conditioned floor area. ^{16,19}	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. Whole-Building Delivered Ventilation			
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.15). ²⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. Controls			
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan) or, if not, controls have been labeled. ²⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. Ventilation Air Intake & Ventilation Source			
7.1 All ventilation air intakes located 150 ft. of setback-clearing distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Except for ventilation air intakes in the wall \geq 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Ventilation air intakes 2 ft. above grade or roof deck in Climate Zones 1-3 or 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, shading, condensing units, or other material at time of inspection. ²⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 Ventilation air intakes provided with rodent / insect screen with \geq 0.5 inch mesh. ²⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. Local Mechanical Exhaust			
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:			
Location	Continuous Rate	Intermittent Rate ³⁰	
8.1 Kitchen	1.5 ACH ₅₀ based on kitchen volume ^{31,32}	\geq 100 CFM and, if not integrated with range, also \geq 5 ACH based on kitchen volume ^{33,34}	<input type="checkbox"/>
8.2 Bathroom	\geq 20 CFM	\geq 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed. ³⁵			<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings. ³⁶			<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain. ³⁷			<input type="checkbox"/>
9. Ventilation & Exhaust Fan Ratings (Exemptions for Kitchen, HVAC, and Remote-Mounted Fans) ³⁸			
9.1 Intermittent supply and exhaust fans rated at 1.3 lpm by mfr when producing no less than the minimum airflow rate required by Section 8 of this Checklist. ³⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Continuous supply & exhaust fans rated at 1 lpm by mfr when producing no less than the minimum airflow required by Section 8 of this Checklist. ⁴⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Bathroom fans used as part of a whole-house mechanical ventilation system that is ENERGY STAR certified, unless rated flow rate \geq 100 CFM. ⁴¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. Combustion Appliances			

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts

- 4.1 Total Rater-measured duct leakage meets one of the following two options: ¹⁶
 - 4.1.1 Rough-in: \leq 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface, Rater-verified at final. ¹⁷
 - 4.1.2 Final: \leq 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register grilles atop the finished surface (e.g., drywall, flooring) installed. ¹⁸
- 4.2 Rater-measured duct leakage to outdoors \leq 4 CFM25 per 100 sq. ft. of conditioned floor area. ^{16,19}

Total Duct leakage target moving to 4 CFM/100sqft
Consistent with the 2012 IECC target



- Tested at rough
 - $4 \leq$ CFM 25 per 100 sqft of conditioned floor area
 - 2000 sqft house
 - 8 CFM = 160 CFM@25 max
 - 6CFM = 120 CFM@25 max
 - 4 CFM = 80 CFM@25 max

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts


4.1 Total Rater-measured duct leakage meets one of the following two options:¹⁶

4.1.1 **Rough-in:** ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface. Rater-verified at final.¹⁷

4.1.2 **Final:** ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register grilles atop the finished surface (e.g., drywall, flooring) installed.¹⁶

4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area.^{16,19}

Footnote 17



- Cabinets (e.g., kitchen, bath, multimedia) or ductwork that connect duct boots to toe-kick registers are not required to be in place during the 'rough-in' test
- Phased in Target
 - Home permitted in 2013 rough-in leakage target is ≤ 6 CFM@25 per 100 sq. ft. of CFA with air handler and all ductwork & duct boots installed
 - For Home permitted in 2014 target is 4 CFM@25




Rater must verify that HVAC supply and return register boots are sealed to subfloor and drywall throughout the house



Total Duct Leakage

Inside and outside the building envelope



Total Duct leakage at Final

- Footnote 18
 - Registers atop carpets are permitted to be removed and the face of the duct boot temporarily sealed during testing.
 - In such cases, the Rater shall visually verify that the boot has been durably sealed to the subfloor (e.g., using duct mastic or caulk) to prevent leakage during normal operation.

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts

4.1 Total Rater-measured duct leakage meets one of the following two options: ¹⁶

4.1.1 Rough-in: ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface, Rater-verified at final. ¹⁷

4.1.2 Final: ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register grilles atop the finished surface (e.g., drywall, flooring) installed. ¹⁶

4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ^{16,19}

Getting to 4 CFM


- We are seeing it now – Consistency is the issue
- Seal every seam




Duct Leakage to Outside



≤ 4 CFM 25 per 100 sqft of conditioned floor area
2000 sqft house ≤ 80 CFM 25 total




Duct Leakage to Outside



- Use blower door to pressurize house and ducts to +25 Pa wrt outside
- Duct leakage to indoors eliminated




Duct Leakage to Outside



- Turn on duct tester fan
- Goal: Match the CFM of the blower door air leaving the ducts



Duct Leakage to Outside



- Adjust duct tester to 0.0 Pa ductwork wrt house
- Measure duct tester airflow (CFM)
- Report as 103 CFM25 duct leakage to outdoors



HVAC Rater's Checklist Section #4

Footnote #19

- For homes that have ≤ 1,200 sq. ft. of conditioned floor area, measured duct leakage to outdoors shall be ≤ 5 CFM25 per 100 sq. ft. of conditioned floor area
- Testing of duct leakage to outside can be waived if:
 - All ducts & air handling equipment are located within the thermal envelope
 - Envelope leakage has been tested to be ≤ to half of the Prescriptive Path infiltration limit for the Climate Zone where the home is to be built (2 ACH50 in climate zone 5)
 - Total duct leakage is ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area, or ≤ 5 CFM25 per 100 sq. ft. of conditioned floor area for homes that have less than 1,200 sq. ft. of conditioned floor area



HVAC Rater Checklist Section #5

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist

4. Duct Leakage - Applies to All Heating, Cooling, and Exhaust Ventilation Ducts

5. Whole-Building Delivered Ventilation

5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.11). 20

Item	Must Comply	Rater Verified	Yes	No
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.11). ²⁰			<input type="checkbox"/>	<input type="checkbox"/>
B. Controls				
B.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²¹			<input type="checkbox"/>	<input type="checkbox"/>
B.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²²			<input type="checkbox"/>	<input type="checkbox"/>
B.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²³			<input type="checkbox"/>	<input type="checkbox"/>
B.4 Continuously operating ventilation & exhaust fans include readily accessible override controls. ²⁴			<input type="checkbox"/>	<input type="checkbox"/>
B.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan) or, if not, controls have been labeled. ²⁵			<input type="checkbox"/>	<input type="checkbox"/>
7. Ventilation Air Intake & Ventilation Sources				
7.1 All ventilation air intake is located ≥10 ft. of unobstructed distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air intakes in the wall ≥ 3 ft. from dryer exhausts and contamination sources existing through the roof. ²⁶			<input type="checkbox"/>	<input type="checkbox"/>
7.2 Ventilation air intakes ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units, or other material at time of inspection. ²⁶			<input type="checkbox"/>	<input type="checkbox"/>
7.3 Ventilation air intakes provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁶			<input type="checkbox"/>	<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from garages, unadorned porches, or attics. ²⁶			<input type="checkbox"/>	<input type="checkbox"/>
8. Local Mechanical Exhaust				
In each kitchen and bathroom (excluding bedrooms), a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:				
Location	Continuous Rate	Intermittent Rate		
Kitchen	≥ 1 ACH ₅₀ based on kitchen volume. ^{27,28}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH ₅₀ based on kitchen volume. ^{27,28}	<input type="checkbox"/>	<input type="checkbox"/>
Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>	<input type="checkbox"/>
B.3 If fans share common exhaust duct, back-draft dampers installed.				
B.4 Common exhaust duct not shared by fans in separate dwellings.				
B.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.				
9. Ventilation & Exhaust Fan Ratings (Exceptions for Kitchen, HVAC, and Remote-Mounted Fans)²⁹				
9.1 Intermittent supply & exhaust fans rated at ≥ 3 cfm by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM.			<input type="checkbox"/>	<input type="checkbox"/>
9.2 Continuous supply & exhaust fans rated at ≥ 1 cfm by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist.			<input type="checkbox"/>	<input type="checkbox"/>
9.3 Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified; unless rated flow rate ≥ 50 CFM.			<input type="checkbox"/>	<input type="checkbox"/>
10. Combustion Appliances				
10.1 Furnaces, boilers, and water heaters located within the home's pressure boundary are mechanically drafted or direct-vented. As an exception, naturally drafted equipment is allowed in Climate Zones 1-3. For naturally drafted furnaces, boilers, and water heaters, the Rater has followed REDNET's BPH combustion safety test procedure and met the selected standard's limits for depressurization, spillage, draft pressure, and CO concentration in ambient air, as well as an CO concentration in the flue of ≤ 25 ppm. ³⁰			<input type="checkbox"/>	<input type="checkbox"/>
10.2 For appliances that are not mechanically drafted or direct-vented to outdoors, total net rated exhaust flow of the two largest exhaust fans (excluding summer cooling fans) is ≥ 15 CFM per 100 sq. ft. of occupiable space when at full capacity or the Rater has verified that the pressure differential is ≤ -0.5 Pa using BPH's or REDNET's worst-case depressurization test procedure. ³⁰			<input type="checkbox"/>	<input type="checkbox"/>
10.3 If vented combustion appliances other than cooking ranges or ovens are located inside the home's pressure boundary, the Rater has operated the appliance for at least 10 minutes and verified that the ambient CO level does not exceed 30 ppm. ³⁰			<input type="checkbox"/>	<input type="checkbox"/>
11. Filtration				
11.1 At least one MERV 8 or higher filter installed in each ducted mechanical system. ³¹			<input type="checkbox"/>	<input type="checkbox"/>
11.2 All return air and mechanically supplied outdoor air pass through filter prior to conditioning.			<input type="checkbox"/>	<input type="checkbox"/>
11.3 Filter located and installed so as to facilitate access and regular service by the owner. ³²			<input type="checkbox"/>	<input type="checkbox"/>
11.4 Filter access panel includes gasket or comparable sealing mechanism and fits snugly against the exposed edge of filter when closed to prevent bypass. ³²			<input type="checkbox"/>	<input type="checkbox"/>

Footnote #20

- The whole-house ventilation air flow and local exhaust air flows shall be measured by the
- Ventilation rate shall be within 100 and 120% of ASHRAE 62.2
- EnergyLogic uses a Flow Box



HVAC Rater Checklist Section #6

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

6. Controls

- 6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan").
- 6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ^{21, 22}
- 6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²¹
- 6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls.
- 6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan) or, if not, controls have been labeled.

Location	Continuous Rate	Intermittent Rate ²²			
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ²³	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{23, 24}		<input type="checkbox"/>	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM		<input type="checkbox"/>	<input type="checkbox"/>
8.3	Fans share common exhaust duct, back-draft dampers installed.			<input type="checkbox"/>	<input type="checkbox"/>
8.4	Common exhaust duct not shared by fans in separate dwellings.			<input type="checkbox"/>	<input type="checkbox"/>
8.5	Closets/dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			<input type="checkbox"/>	<input type="checkbox"/>
9. Ventilation & Exhaust Fan Ratings (Exemptions for Kitchens, HVAC, and Remote-Mounted Fans) ²⁵					
9.1	Intermittent supply and exhaust fans rated at ≥ 3 scores by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM.			<input type="checkbox"/>	<input type="checkbox"/>
9.2	Continuous supply & exhaust fans rated at ≥ 1 score by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist.			<input type="checkbox"/>	<input type="checkbox"/>
9.3	Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified; unless rated flow rate ≥ 50 CFM.			<input type="checkbox"/>	<input type="checkbox"/>
10. Combustion Appliances					
10.1	Furnaces, boilers, and water heaters located within the home's pressure boundary are mechanically drafted or direct-vented. As an exception, naturally drafted equipment is allowed in Climate Zones 1-3. For naturally drafted furnaces, boilers, and water heaters, the Rater has followed RESNET or BPI combustion safety test procedures and met the selected standard's limits for depressurization, spillage, draft pressure, and CO concentration in ambient air, as well as a CO concentration in the flue of ≥ 25 ppm.			<input type="checkbox"/>	<input type="checkbox"/>
10.2	For appliances that are not mechanically drafted or direct-vented to outdoors, total net rated exhaust flow of the two largest exhaust fans (including summer cooling fans) is ≥ 10 CFM per 100 sq. ft. of occupiable space when at full capacity or the Rater has verified that the pressure differential is ≤ -0.5 Pa using BPI's or RESNET's worst-case depressurization test procedure. ^{26, 27}			<input type="checkbox"/>	<input type="checkbox"/>
10.3	If vented combustion appliances other than cooking ranges or ovens are located inside the home's pressure boundary, the Rater has operated the appliance for at least 10 minutes and verified that the ambient CO level does not exceed 30 ppm. ²⁸			<input type="checkbox"/>	<input type="checkbox"/>
11. Filtration					
11.1	At least one MERV 8 or higher filter installed in each ducted mechanical system. ²⁹			<input type="checkbox"/>	<input type="checkbox"/>
11.2	All return air and mechanically supplied outdoor air pass through filter prior to conditioning.			<input type="checkbox"/>	<input type="checkbox"/>
11.3	Filter located and installed so as to facilitate access and regular service by the owner. ³⁰			<input type="checkbox"/>	<input type="checkbox"/>
11.4	Filter access panel includes gasket or comparable sealing mechanism and fits snugly against the exposed edge of filter when closed to prevent bypass. ³¹			<input type="checkbox"/>	<input type="checkbox"/>

Footnote #21

- In cases where the condenser unit is installed after the time of inspection by the Rater, the Rater is exempt from verifying Item 6.2 when the condenser is for an AC unit and also Item 6.3 when the condenser is for a heat pump unit



HVAC Rater Checklist Section #6

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

6. Controls

- 6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan").
- 6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ^{21, 22}
- 6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²¹
- 6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls.
- 6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan) or, if not, controls have been labeled.

Location	Continuous Rate	Intermittent Rate ²²			
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ²³	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{23, 24}		<input type="checkbox"/>	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM		<input type="checkbox"/>	<input type="checkbox"/>
8.3	Fans share common exhaust duct, back-draft dampers installed.			<input type="checkbox"/>	<input type="checkbox"/>
8.4	Common exhaust duct not shared by fans in separate dwellings.			<input type="checkbox"/>	<input type="checkbox"/>
8.5	Closets/dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			<input type="checkbox"/>	<input type="checkbox"/>
9. Ventilation & Exhaust Fan Ratings (Exemptions for Kitchens, HVAC, and Remote-Mounted Fans) ²⁵					
9.1	Intermittent supply and exhaust fans rated at ≥ 3 scores by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM.			<input type="checkbox"/>	<input type="checkbox"/>
9.2	Continuous supply & exhaust fans rated at ≥ 1 score by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist.			<input type="checkbox"/>	<input type="checkbox"/>
9.3	Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified; unless rated flow rate ≥ 50 CFM.			<input type="checkbox"/>	<input type="checkbox"/>
10. Combustion Appliances					
10.1	Furnaces, boilers, and water heaters located within the home's pressure boundary are mechanically drafted or direct-vented. As an exception, naturally drafted equipment is allowed in Climate Zones 1-3. For naturally drafted furnaces, boilers, and water heaters, the Rater has followed RESNET or BPI combustion safety test procedures and met the selected standard's limits for depressurization, spillage, draft pressure, and CO concentration in ambient air, as well as a CO concentration in the flue of ≥ 25 ppm.			<input type="checkbox"/>	<input type="checkbox"/>
10.2	For appliances that are not mechanically drafted or direct-vented to outdoors, total net rated exhaust flow of the two largest exhaust fans (including summer cooling fans) is ≥ 10 CFM per 100 sq. ft. of occupiable space when at full capacity or the Rater has verified that the pressure differential is ≤ -0.5 Pa using BPI's or RESNET's worst-case depressurization test procedure. ^{26, 27}			<input type="checkbox"/>	<input type="checkbox"/>
10.3	If vented combustion appliances other than cooking ranges or ovens are located inside the home's pressure boundary, the Rater has operated the appliance for at least 10 minutes and verified that the ambient CO level does not exceed 30 ppm. ²⁸			<input type="checkbox"/>	<input type="checkbox"/>
11. Filtration					
11.1	At least one MERV 8 or higher filter installed in each ducted mechanical system. ²⁹			<input type="checkbox"/>	<input type="checkbox"/>
11.2	All return air and mechanically supplied outdoor air pass through filter prior to conditioning.			<input type="checkbox"/>	<input type="checkbox"/>
11.3	Filter located and installed so as to facilitate access and regular service by the owner. ³⁰			<input type="checkbox"/>	<input type="checkbox"/>
11.4	Filter access panel includes gasket or comparable sealing mechanism and fits snugly against the exposed edge of filter when closed to prevent bypass. ³¹			<input type="checkbox"/>	<input type="checkbox"/>

Footnote #22

- To prevent potential equipment damage, the Rater shall not conduct this test if the outdoor temperature is ≤ 55°F or, if known, below the manufacturer-recommended minimum operating temperature for the cooling cycle
- When this occurs, the Rater shall mark 'N/A' on the Checklist for this item



HVAC Rater Checklist Section #7

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts		Must Comply	Rater Verified	Yes
4.1 Total Rater-measured duct leakage meets one of the following two options: ²²				
4.1.1 Rough-in ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed, in addition, all duct boots sealed to finished surface. Rater verified at time of inspection. ²²				<input type="checkbox"/>
4.1.2 Final ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register gaskets and the finished surface (e.g. drywall, flooring, impales). ²²				<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ²²				<input type="checkbox"/>
5. Whole-Building Delivered Ventilation				
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.11). ²³				<input type="checkbox"/>
6. Controls				
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²⁴				<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²⁴				<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²⁴				<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ²⁴				<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan or, if not, controls have been labeled). ²⁴				<input type="checkbox"/>
7. Ventilation Air Inlets & Ventilation Source				
7.1 All ventilation air inlets located ≥10 ft. of stretched-string distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air inlets in the wall ≥ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²³				<input type="checkbox"/>
7.2 Ventilation air inlets ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units or other material at time of inspection. ²⁴				<input type="checkbox"/>
7.3 Ventilation air inlets provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁵				<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁵				<input type="checkbox"/>
8. Local Mechanical Exhaust				
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:				
Location	Continuous Rate	Intermittent Rate ²⁶		
8.1 Kitchen	≥ 1 SACH, based on kitchen volume ^{26,27}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{26,27}		<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM		<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed.				<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings.				<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.				<input type="checkbox"/>
9. Ventilation & Exhaust Fan Ratings (Exceptions for Kitchens, HVAC, and Remote-Mounted Fans) ²⁸				
9.1 Intermittent supply and exhaust fans rated at ≥ 3 cfm by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM.				<input type="checkbox"/>
9.2 Continuous supply & exhaust fans rated at ≥ 1 cfm by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist.				<input type="checkbox"/>
9.3 Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified, unless rated flow rate ≥ 500 CFM.				<input type="checkbox"/>
10. Combustion Appliances				

Footnote #23

- The outlet and inlet of balanced ventilation systems shall meet these spacing requirements unless manufacturer instructions indicate that a smaller distance may be used
- However, if this occurs the manufacturer's instructions shall be collected for documentation purposes.

7. Ventilation Air Inlets & Ventilation Source

- 7.1 All ventilation air inlets located ≥10 ft. of stretched-string distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air inlets in the wall ≥ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²³
- 7.2 Ventilation air inlets ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units or other material at time of inspection. ²⁴
- 7.3 Ventilation air inlets provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁵
- 7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁵

HVAC Rater Checklist Section #7

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts		Must Comply	Rater Verified	Yes
4.1 Total Rater-measured duct leakage meets one of the following two options: ²²				
4.1.1 Rough-in ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed, in addition, all duct boots sealed to finished surface. Rater verified at time of inspection. ²²				<input type="checkbox"/>
4.1.2 Final ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register gaskets and the finished surface (e.g. drywall, flooring, impales). ²²				<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ²²				<input type="checkbox"/>
5. Whole-Building Delivered Ventilation				
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.11). ²³				<input type="checkbox"/>
6. Controls				
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²⁴				<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²⁴				<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²⁴				<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ²⁴				<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan or, if not, controls have been labeled). ²⁴				<input type="checkbox"/>
7. Ventilation Air Inlets & Ventilation Source				
7.1 All ventilation air inlets located ≥10 ft. of stretched-string distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air inlets in the wall ≥ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²³				<input type="checkbox"/>
7.2 Ventilation air inlets ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units or other material at time of inspection. ²⁴				<input type="checkbox"/>
7.3 Ventilation air inlets provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁵				<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁵				<input type="checkbox"/>
8. Local Mechanical Exhaust				
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:				
Location	Continuous Rate	Intermittent Rate ²⁶		
8.1 Kitchen	≥ 1 SACH, based on kitchen volume ^{26,27}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{26,27}		<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM		<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed.				<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings.				<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.				<input type="checkbox"/>
9. Ventilation & Exhaust Fan Ratings (Exceptions for Kitchens, HVAC, and Remote-Mounted Fans) ²⁸				
9.1 Intermittent supply and exhaust fans rated at ≥ 3 cfm by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM.				<input type="checkbox"/>
9.2 Continuous supply & exhaust fans rated at ≥ 1 cfm by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist.				<input type="checkbox"/>
9.3 Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified, unless rated flow rate ≥ 500 CFM.				<input type="checkbox"/>
10. Combustion Appliances				

Footnote #24

- The minimum required height in North Carolina for Climate Zone 4 will be reduced from 4 feet to 2 feet and in Climate Zone 5 from 4 feet to 2.5 feet based on historical snowfall data for this state
- Note that EPA is evaluating the potential to reduce inlet heights in other regions based upon historical snowfall data

7. Ventilation Air Inlets & Ventilation Source

- 7.1 All ventilation air inlets located ≥10 ft. of stretched-string distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air inlets in the wall ≥ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²³
- 7.2 Ventilation air inlets ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units or other material at time of inspection. ²⁴
- 7.3 Ventilation air inlets provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁵
- 7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁵

HVAC Rater Checklist Section #7

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts	Must Correct	Rater Verified	Yes
4.1 Total Rater-measured duct leakage meets one of the following two options: ²¹			
4.1.1 Rough-in ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed; in addition, all duct boots sealed to finished surface. Rater verified at final. ²²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.1.2 Final ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register gaskets seal the finished surface (e.g., drywall, flooring, impales). ²²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ²²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. Whole-Building Delivered Ventilation			
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.1). ²³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. Controls			
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan) or, if not, controls have been labeled. ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. Ventilation Air Inlets & Ventilation Source			
7.1 All ventilation air inlets located ≥10 ft. of stretched-string distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air inlets in the wall ≥ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Ventilation air inlets ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units or other material at time of inspection. ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 Ventilation air inlets provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. Local Mechanical Exhaust			
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:			
Location	Continuous Rate	Intermittent Rate ²⁶	
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed.			<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²			<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			<input type="checkbox"/>

Footnote #25

- Without proper maintenance, ventilation air inlet screens often become filled with debris
- Therefore, EPA recommends, but does not require, that these ventilation air inlets be located so as to facilitate access and regular service by the owner

7. Ventilation Air Inlets & Ventilation Source

- 7.1 All ventilation air inlets located ≥10 ft. of stretched-string distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air inlets in the wall ≥ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²⁵
- 7.2 Ventilation air inlets ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units or other material at time of inspection. ²⁴
- 7.3 Ventilation air inlets provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁵
- 7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁵

HVAC Rater Checklist Section #8

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts	Must Correct	Rater Verified	Yes
4.1 Total Rater-measured duct leakage meets one of the following two options: ²¹			
4.1.1 Rough-in ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed; in addition, all duct boots sealed to finished surface. Rater verified at final. ²²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.1.2 Final ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register gaskets seal the finished surface (e.g., drywall, flooring, impales). ²²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ²²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. Whole-Building Delivered Ventilation			
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.1). ²³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. Controls			
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan) or, if not, controls have been labeled. ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. Ventilation Air Inlets & Ventilation Source			
7.1 All ventilation air inlets located ≥10 ft. of stretched-string distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air inlets in the wall ≥ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ²⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Ventilation air inlets ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units or other material at time of inspection. ²⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 Ventilation air inlets provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ²⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. Local Mechanical Exhaust			
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards: ^{20,25,27}			
Location	Continuous Rate	Intermittent Rate ²⁸	
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed.			<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²			<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			<input type="checkbox"/>

Footnote #26 & 27

- Per ASHRAE 62.2-2010, an exhaust system is one or more fans that remove air from the building, causing outdoor air to enter by ventilation inlets or normal leakage paths through the building envelope (e.g., bath exhaust fans, range hoods, clothes dryers)
- Per ASHRAE 62.2-2010, a bathroom is any room containing a bathtub, shower, spa, or similar source of moisture

8. Local Mechanical Exhaust

In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards: ^{20,25,27}

Location	Continuous Rate	Intermittent Rate ²⁸	
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed.			<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²			<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			<input type="checkbox"/>

HVAC Rater Checklist Section #8

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

Item	Must Comply	Minor Violation	Not
4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts			
4.1 Total Rate-measured duct leakage meets one of the following two options:			
4.1.1 Rough-in: ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface. Rate verified at final.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.1.2 Final: ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register grilles along the finished surface (e.g. drywall, flooring, trim).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Rate-measured duct leakage to outdoors: ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. Whole-Building Delivered Ventilation			
5.1 Rate-measured ventilation rate is within 100-120% of HVAC contractor design value (2.1). ²⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. Controls			
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan").	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²⁷	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan or, if not, controls have been labeled).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. Ventilation Air Intake & Ventilation Source			
7.1 All ventilation air vents located ≥ 10 ft. of unobstructing distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air intakes in the wall ≥ 3 ft. from dryer exhausts and contamination sources ending through the roof.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Ventilation air intakes ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensate units or other material at time of inspection. ²⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 Ventilation air intakes provided with rodent / insect screen with ≤ 0.5 inch mesh. ²⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. Local Mechanical Exhaust			
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rate-measured airflow standards: ^{20,26,27}			
Location	Continuous Rate	Intermittent Rate ²⁸	
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed.			
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²			
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			

Footnote #28

- An intermittent mechanical exhaust system shall be designed to operate as needed by the occupant
- Control devices shall not impede occupant control in intermittent systems

HVAC Rater Checklist Section #8



- For homes permitted through 01/01/2014:
- Homes are permitted to be certified without enforcement of this Item to provide partners with additional time to integrate this feature into their homes.

8. Local Mechanical Exhaust

In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rate-measured airflow standards:^{20,26,27}

Location	Continuous Rate	Intermittent Rate ²⁸	
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed.			
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²			
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			

HVAC Rater Checklist Section #8

For homes permitted on or after 01/01/2014:

- Homes shall meet this Item.
- Alternatively, the prescriptive duct sizing requirements in Table 5.3 of ASHRAE 62.2-2010 are permitted to be used for kitchen exhaust fans based upon the rated airflow of the fan at 0.25 IWC.
- If the rated airflow is unknown, ≥ 6 in. smooth duct shall be used, with a rectangular to round duct transition as needed.**
- Guidance to assist partners with these alternatives is available at www.energystar.gov/newhomesresources.
- As an alternative to Item 8.1, homes that are PHIUS+ certified are permitted to use a continuous kitchen exhaust rate of 25 CFM per 2009 IRC Table M1507.3.



8. Local Mechanical Exhaust

In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:^{20,25,27}

Location	Continuous Rate	Intermittent Rate ²⁶		
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>	
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>	
8.3 If fans share common exhaust duct, back-draft dampers installed.				
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²				
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.				



HVAC Rater Checklist Section #8

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist¹

Location	Continuous Rate	Intermittent Rate ²⁶		
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>	
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>	
8.3 If fans share common exhaust duct, back-draft dampers installed.				
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²				
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.				

8. Local Mechanical Exhaust

In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:^{20,25,27}

Location	Continuous Rate	Intermittent Rate ²⁶		
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,30}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>	
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>	
8.3 If fans share common exhaust duct, back-draft dampers installed.				
8.4 Common exhaust duct not shared by fans in separate dwellings. ³²				
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.				

Footnote #31

- All intermittent kitchen exhaust fans must be capable of exhausting at least 100 CFM.
- In addition, if the fan is not part of a vented range hood or appliance-range hood combination (i.e., if the fan is not integrated with the range), then it must also be capable of exhausting ≥ 5 ACH, based on the kitchen volume.

HVAC Rater Checklist Section #8

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts	Must Comply	Rater Verified	Yes
4.1 Total Rater-measured duct leakage meets one of the following two options: ²⁰			<input type="checkbox"/>
4.1.1 Rough-in ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface. Rater verified as final. ²¹			<input type="checkbox"/>
4.1.2 Final ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register gaskets and the finished surface (e.g. drywall, flooring) installed. ²²			<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ²³			<input type="checkbox"/>
5. Whole-Building Delivered Ventilation ²⁴			<input type="checkbox"/>
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.1). ²⁵			<input type="checkbox"/>
6. Controls			<input type="checkbox"/>
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²⁶			<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²⁷			<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²⁸			<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ²⁹			<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan or, if not, controls have been labeled).			<input type="checkbox"/>
7. Ventilation Air Intake & Ventilation Sources			<input type="checkbox"/>
7.1 All ventilation air intake is located ≥10 ft. of unobstructed distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air intakes in the wall ≤ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ³⁰			<input type="checkbox"/>
7.2 Ventilation air intakes ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units, or other material at time of inspection. ³¹			<input type="checkbox"/>
7.3 Ventilation air intakes provided with rodent / insect screen with ≤ 0.5 inch mesh. ³²			<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ³³			<input type="checkbox"/>
8. Local Mechanical Exhaust			<input type="checkbox"/>

Footnote #29

- Kitchen volume shall be determined by drawing the smallest possible rectangle on the floor plan that encompasses all cabinets, pantries, islands, and peninsulas and multiplying by the average ceiling height for this area.
- Cabinet volume shall be included in the kitchen volume calculation.

8. Local Mechanical Exhaust

In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards: ^{20,25,27}

9. Ventilation & Exhaust Fan Ratings (Exemptions for HVAC and Remote-Mounted Fans) ³⁰

- 9.1 Intermittent supply and exhaust fans rated at ≤ 3 sones by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM.
- 9.2 Continuous supply & exhaust fans rated at ≤ 1 sone by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist.
- 9.3 Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR qualified; unless rated flow rate ≥ 500 CFM.

HVAC Rater Checklist Section #8

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts	Must Comply	Rater Verified	Yes
4.1 Total Rater-measured duct leakage meets one of the following two options: ²⁰			<input type="checkbox"/>
4.1.1 Rough-in ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface. Rater verified as final. ²¹			<input type="checkbox"/>
4.1.2 Final ≤ 8 CFM25 per 100 sq. ft. of CFA with the air handler and all ductwork, building cavities used as ductwork, duct boots, & register gaskets and the finished surface (e.g. drywall, flooring) installed. ²²			<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ²³			<input type="checkbox"/>
5. Whole-Building Delivered Ventilation ²⁴			<input type="checkbox"/>
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.1). ²⁵			<input type="checkbox"/>
6. Controls			<input type="checkbox"/>
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ²⁶			<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ²⁷			<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ²⁸			<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ²⁹			<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan or, if not, controls have been labeled).			<input type="checkbox"/>
7. Ventilation Air Intake & Ventilation Sources			<input type="checkbox"/>
7.1 All ventilation air intake is located ≥10 ft. of unobstructed distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air intakes in the wall ≤ 3 ft. from dryer exhausts and contamination sources exiting through the roof. ³⁰			<input type="checkbox"/>
7.2 Ventilation air intakes ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, plantings, condensing units, or other material at time of inspection. ³¹			<input type="checkbox"/>
7.3 Ventilation air intakes provided with rodent / insect screen with ≤ 0.5 inch mesh. ³²			<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ³³			<input type="checkbox"/>
8. Local Mechanical Exhaust			<input type="checkbox"/>

Footnote #32

- Exhaust outlets from more than one dwelling unit may be served by a single exhaust fan if the fan runs continuously or if each outlet has a back-draft damper to prevent cross-contamination when the fan is not running

8. Local Mechanical Exhaust

In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards: ^{20,25,27}

Location	Continuous Rate	Intermittent Rate ²⁸		
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{29,31}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{29,30,31}	<input type="checkbox"/>	
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>	
8.3 If fans share common exhaust duct, back-draft dampers installed.			<input type="checkbox"/>	
8.4 Common exhaust duct not shared by fans in separate dwellings.			<input type="checkbox"/>	
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain.			<input type="checkbox"/>	

HVAC Rater Checklist Section #9

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
HVAC System Quality Installation Rater Checklist ¹

4. Duct Leakage - Applies to All Heating, Cooling, and Balanced Ventilation Ducts	Must Correct	Minor Violation	Pass
4.1 Total Rater-measured duct leakage meets one of the following two options: ¹			
4.1.1 Rough-in ≤ 4 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, & duct boots installed. In addition, all duct boots sealed to finished surface. Rater verified air flow. ²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.1.2 Final ≤ 8 CFM25 per 100 sq. ft. of CFA with air handler and all ductwork, building cavities used as ductwork, duct boots, & register grilles sealed to finished surface (e.g. drywall, flooring, trim). ²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Rater-measured duct leakage to outdoors ≤ 4 CFM25 per 100 sq. ft. of conditioned floor area. ²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. Whole-Building Delivered Ventilation			
5.1 Rater-measured ventilation rate is within 100-120% of HVAC contractor design value (2.1 h). ³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. Controls			
6.1 Air flow is produced when central HVAC fan is energized (set thermostat to "fan"). ⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.2 Cool air flow is produced when the cooling cycle is energized (set thermostat to "cool"). ⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.3 Heated air flow is produced when the heating cycle is energized (set thermostat to "heat"). ⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.4 Continuously-operating ventilation & exhaust fans include readily accessible override controls. ⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.5 Function of ventilation controls is obvious (e.g., bathroom exhaust fan or, if not, controls have been labeled). ⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. Ventilation Air Intake & Ventilation Sources			
7.1 All ventilation air vents located ≥10 ft. of unobstructing distance from known contamination sources such as stack, vent, exhaust hood, or vehicle exhaust. Exception: ventilation air intakes in the wall ≥ 3 ft. from dryer exhausts and contamination sources ending through the roof. ⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.2 Ventilation air intakes ≥ 2 ft. above grade or roof deck in Climate Zones 1-3 or ≥ 4 ft. above grade or roof deck in Climate Zones 4-8 and not obstructed by snow, planting, landscaping, or other material at time of inspection. ⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.3 Ventilation air intakes provided with rodent / insect screen with ≤ 0.5 inch mesh. ⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7.4 Ventilation air comes directly from outdoors, not from adjacent dwelling units, garages, crawlspaces, or attics. ⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. Local Mechanical Exhaust			
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:			
Location	Continuous Rate	Intermittent Rate ⁷	
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{8,9}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{8,9}	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed. ¹⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings. ¹⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain. ¹¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. Ventilation & Exhaust Fan Ratings (Exemptions for Kitchen, HVAC, and Remote-Mounted Fans) ¹²			
9.1 Intermittent supply and exhaust fans rated at ≥ 3 sones by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM. ¹³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Continuous supply & exhaust fans rated at ≤ 1 sone by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist. ¹³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified; unless rated flow rate ≥ 500 CFM. ¹⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Footnote #33

- Fans exempted from this requirement include HVAC air handlers and remote-mounted fans
- To be considered for this exemption, a remote-mounted fan must be mounted outside the habitable spaces, bathrooms, toilets, and hallways and there shall be ≥ 4 ft. ductwork between the fan and intake grill
- Per ASHRAE 62.2-2010, habitable spaces are intended for continual human occupancy; such space generally includes areas used for living, sleeping, dining, and cooking but does not generally include bathrooms, toilets, hallways, storage areas, closets, or utility rooms

9. Ventilation & Exhaust Fan Ratings (Exemptions for Kitchen, HVAC, and Remote-Mounted Fans) ¹⁵
9.1 Intermittent supply and exhaust fans rated at ≤ 3 sones by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM. ¹³
9.2 Continuous supply & exhaust fans rated at ≤ 1 sone by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist. ¹³
9.3 Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified; unless rated flow rate ≥ 500 CFM. ¹⁴

HVAC Rater Checklist Section #10

10. Combustion Appliances

10.1 Furnaces, boilers, and water heaters located within the home's pressure boundary are mechanically drafted or direct-vented. As an exception, naturally drafted equipment is allowed in Climate Zones 1-3. For naturally drafted furnaces, boilers, and water heaters, the Rater has followed RESNET or BPI combustion safety test procedures and met the selected standard's limits for depressurization, spillage, draft pressure, and CO concentration in ambient air, as well as a CO concentration in the flue of ≤ 25 ppm. ^{16,25,36}
10.2 For fireplaces that are not mechanically drafted or direct-vented to outdoors, total net rated exhaust flow of the two largest exhaust fans (excluding summer cooling fans) is ≤ 15 CFM per 100 sq. ft. of occupiable space when at full capacity or the Rater has verified that the pressure differential is ≤ -5 Pa using BPI's or RESNET's worst-case depressurization test procedure. ^{26,36,37,38}
10.3 If unvented combustion appliances other than cooking ranges or ovens are located inside the home's pressure boundary, the Rater has operated the appliance for at least 10 minutes and verified that the ambient CO level does not exceed 35 ppm. ³⁹

8. Local Mechanical Exhaust	Must Correct	Minor Violation	Pass
In each kitchen and bathroom, a system shall be installed that exhausts directly to the outdoors and meets one of the following Rater-measured airflow standards:			
Location	Continuous Rate	Intermittent Rate ⁷	
8.1 Kitchen	≥ 5 ACH, based on kitchen volume ^{8,9}	≥ 100 CFM and, if not integrated with range, also ≥ 5 ACH based on kitchen volume ^{8,9}	<input type="checkbox"/>
8.2 Bathroom	≥ 20 CFM	≥ 50 CFM	<input type="checkbox"/>
8.3 If fans share common exhaust duct, back-draft dampers installed. ¹⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.4 Common exhaust duct not shared by fans in separate dwellings. ¹⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8.5 Clothes dryers vented directly to outdoors, except for ventless dryers equipped with a condensate drain. ¹¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. Ventilation & Exhaust Fan Ratings (Exemptions for Kitchen, HVAC, and Remote-Mounted Fans) ¹²			
9.1 Intermittent supply and exhaust fans rated at ≥ 3 sones by mfr. when producing no less than the minimum airflow rate required by Section 8 of this Checklist, unless rated flow ≥ 400 CFM. ¹³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.2 Continuous supply & exhaust fans rated at ≤ 1 sone by mfr. when producing no less than the minimum airflow required by Section 8 of this Checklist. ¹³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.3 Bathroom fans used as part of a whole-house mechanical ventilation system shall be ENERGY STAR certified; unless rated flow rate ≥ 500 CFM. ¹⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. Combustion Appliances			
10.1 Furnaces, boilers, and water heaters located within the home's pressure boundary are mechanically drafted or direct-vented. As an exception, naturally drafted equipment is allowed in Climate Zones 1-3. For naturally drafted furnaces, boilers, and water heaters, the Rater has followed RESNET or BPI combustion safety test procedures and met the selected standard's limits for depressurization, spillage, draft pressure, and CO concentration in ambient air, as well as a CO concentration in the flue of ≤ 25 ppm. ^{16,25,36}	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10.2 For fireplaces that are not mechanically drafted or direct-vented to outdoors, total net rated exhaust flow of the two largest exhaust fans (excluding summer cooling fans) is ≤ 15 CFM per 100 sq. ft. of occupiable space when at full capacity or the Rater has verified that the pressure differential is ≤ -5 Pa using BPI's or RESNET's worst-case depressurization test procedure. ^{26,36,37,38}	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10.3 If unvented combustion appliances other than cooking ranges or ovens are located inside the home's pressure boundary, the Rater has operated the appliance for at least 10 minutes and verified that the ambient CO level does not exceed 35 ppm. ³⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. Filtration			
11.1 At least one MERV 8 or higher filter installed in each ducted mechanical system. ⁴⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11.2 All return air and mechanically supplied outdoor air pass through filter prior to conditioning. ⁴⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11.3 Filter located and installed so as to facilitate access and regular service by the owner. ⁴⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11.4 Filter access panel includes gasket or comparable sealing mechanism and fits snugly against the engaged edge of filter when closed to prevent bypass. ⁴⁰	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Footnote #34

- Per the 2009 International Mechanical Code, a direct-vent appliance is one that is constructed and installed so that all air for combustion is derived from the outdoor atmosphere and all flue gases are discharged to the outside atmosphere
- A mechanical draft system is a venting system designed to remove flue or vent gases by mechanical means consisting of an induced draft portion under non-positive static pressure or a forced draft portion under positive static pressure
- A natural draft system is a venting system designed to remove flue or vent gases under non-positive static vent pressure entirely by natural draft

HVAC Rater Checklist Section #11

11. Filtration

- 11.1 At least one MERV 6 or higher filter installed in each ducted mechanical system.⁴⁰
- 11.2 All return air and mechanically supplied outdoor air pass through filter prior to conditioning.
- 11.3 Filter located and installed so as to facilitate access and regular service by the owner.⁴¹
- 11.4 Filter access panel includes gasket or comparable sealing mechanism and fits snugly against the exposed edge of filter when closed to prevent bypass.⁴²



Footnote #40

- Per ASHRAE 62.2-2010, ducted mechanical systems are those that supply air to an occupiable space through ductwork exceeding 10 ft. in length and through a thermal conditioning component, except for evaporative coolers
- Systems that do not meet this definition are exempt from this requirement
- Also, mini-split systems typically do not have MERV-rated filters available for use and are, therefore, exempted under this version of the guidelines



HVAC Rater Checklist Section #11

11. Filtration

- 11.1 At least one MERV 6 or higher filter installed in each ducted mechanical system.⁴⁰
- 11.2 All return air and mechanically supplied outdoor air pass through filter prior to conditioning.
- 11.3 Filter located and installed so as to facilitate access and regular service by the owner.⁴¹
- 11.4 Filter access panel includes gasket or comparable sealing mechanism and fits snugly against the exposed edge of filter when closed to prevent bypass.⁴²



Footnote #41

- HVAC filters located in the attic shall be considered accessible to the owner if drop-down stairs provide access to attic and a permanently installed walkway has been provided between the attic access location and the filter



HVAC Rater Checklist Section #11

11. Filtration

11.1 At least one MERV 6 or higher filter installed in each ducted mechanical system. ⁴⁰

11.2 All return air and mechanically supplied outdoor air pass through filter prior to conditioning.

11.3 Filter located and installed so as to facilitate access and regular service by the owner. ⁴¹

11.4 Filter access panel includes gasket or comparable sealing mechanism and fits snugly against the exposed edge of filter when closed to prevent bypass. ⁴²




Footnote #42

- The filter media box (i.e., the component in the HVAC system that houses the filter) may be either site-fabricated by the installer or pre-fabricated by the manufacturer to meet this requirement
- These requirements only apply when the filter is installed in a filter media box located in the HVAC system, not when the filter is installed flush with the return grill



Get Started Today!

Join	a credentialing program www.energystar.gov/newhomesHVAC
Find	builder partners www.energystar.gov/partnerlocator
Read	the technical guidelines www.energystar.gov/newhomesguidelines
Ask	questions energystarhomes@energystar.gov


 [@energystarhomes](https://twitter.com/energystarhomes)


 facebook.com/energystar



H-QUITO

- Currently ACCA and Advanced Energy are the only national EPA-recognized third-party training and oversight organization



http://www.advancedenergy.org/qap/how_to_participate.php


<http://qacontractors.org/new-homes/>



Water Management Checklist

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
Water Management System Builder Checklist^{1,2}

Home Address	City	State	Zip Code	Must Contact	Builder Verified	Rater Verified	N/A
1. Water-Managed Site and Foundation							
1.1 Patio slabs, porch slabs, walls, and driveways sloped \pm 0.25 in. per ft. away from home to edge of surface or 10 ft., whichever is less.							
1.2 Backfill has been tamped and that grade sloped \pm 0.5 in. per ft. away from home for a 10 ft. See Footnote for alternatives.							
1.3 Capillary break beneath all slabs (e.g., slab on grade, basement slab) except crawlspace slabs using either: 2.0 mil polyethylene sheeting, lapped 6-12 in., or 1 in. extruded polystyrene insulation with taped joints.							
1.4 Capillary break at all crawlspace floors using \geq 6 mil polyethylene sheeting, lapped 6-12 in., & installed using one of the following options: ^{1,1,1}							
1.4.1 Placed beneath a concrete slab. OR							
1.4.2 Lapped up each wall or pier and fastened with furring strips or equivalent. OR,							
1.4.3 Secured in the ground at the perimeter using slabs.							
1.5 Exterior surface of below-grade walls of basements & unvented crawlspaces finished as follows: ¹							
a) For poured concrete masonry, & insulated concrete forms, finish with damp-proofing coating. ¹							
b) For wood framed walls, finish with polyethylene and adhesive or other equivalent waterproofing.							
1.6 Class 1 vapor retarder not installed on interior side of air permeable insulation in ext. below-grade walls. ¹							
1.7 Sump pump covers mechanically attached with full gasket seal or equivalent.							
1.8 Drain tile installed at the exterior side of footings of basement and crawlspace walls, with the top of the drain tile pipe below the bottom of the concrete slab or crawlspace floor. Drain tile surrounded with 3 in. of 1/2 to 1-in. washed or clean gravel and with gravel layer fully wrapped with fabric cloth. Drain tile level or sloped to discharge to outside grade (daylight) or to a sump pump.							
2. Water-Managed Wall Assembly							
2.1 Flashing at bottom of exterior walls with weep holes included for masonry veneer and weep screen for stucco cladding systems, or equivalent drainage system. ^{1,1}							
2.2 Fully sealed continuous drainage plane behind exterior cladding that laps over flashing in Item 2.1 and fully sealed at all penetrations. Additional bonded-back drainage plane layer provided behind all stucco and non-structural masonry cladding wall assemblies. ^{1,1,1}							
2.3 Windows and door openings fully flashed. ^{1,1}							
3. Water-Managed Roof Assembly							
3.1 Step and lock-out flashing at all roof-wall intersections, extending \geq 4" on wall surface above roof deck and integrated single-style with drainage plane above; roof collar flashing at all roof penetrations. ^{1,1}							
3.2 For homes that don't have a slab-on-grade foundation and do have expansive or collapsible soils, gutters & downspouts provided that empty to lateral piping that discharges water on sloping final grade \geq 3 ft. from foundation, or to underground drainage system not connected to the foundation drain system that discharges water \geq 10 ft. from foundation. See Footnote for alternatives & exemptions. ^{1,1,1}							
3.3 Self-sealing bituminous membrane or equivalent at all valleys & roof deck penetrations. ¹							
3.4 In 2009 IECC Climate Zones 5 & higher, self-sealing bituminous membrane or equivalent over sheathing at eaves from the edge of the roof line to $>$ 2 ft. up roof deck from the interior plane of the exterior wall. ¹							
4. Water-Managed Building Materials							
4.1 Walk-in carpet not installed within 2.5 ft. of toilets, tubs, and showers.							
4.2 Cement board or equivalent moisture-resistant backing material installed on all walls behind tub and shower enclosures, composed of tile or panel assemblies with caulked joints. Paper-faced backboard shall not be used. ¹							
4.3 In Warm-Humid climates, Class 1 vapor retarders not installed on the interior side of air permeable insulation in above-grade walls, except at shower and tub walls. ¹							
4.4 Building materials with visible signs of water damage or mold not installed or allowed to remain. ^{1,1}							
4.5 Framing members & insulation products having high moisture content not enclosed (e.g., with drywall). ¹							
Builder Employee _____ Date _____							
Builder Signature _____ Date _____							
Builder has completed Builder Checklist in its entirety, except for items that are checked in the Rater Verified column (if any)?							
Rater Signature _____ Date _____							



Water Management Checklist

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
Water Management System Builder Checklist ^{1,2}

1.8 Drain tile installed at the exterior side of footings of basement and crawspace walls, with the top of the drain tile pipe below the bottom of the concrete slab or crawspace floor. Drain tile surrounded with ≥ 6 in. of $\frac{1}{2}$ to $\frac{3}{4}$ in. washed or clean gravel and with gravel layer fully wrapped with fabric cloth. Drain tile level or sloped to discharge to outside grade (daylight) or to a sump pump. ⁹

1.4 Capillary break at all crawspace floors using a 6 mil polyethylene sheeting, lapped 6-12 in., & installed using one of the following per ^{1,11} :	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.1 Placed beneath a concrete slab, OR	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.2 Lapped up each wall or pier and fastened with furring strips or equivalent, OR	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.3 Secured in the ground at the perimeter using stakes.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 Exterior surface of below-grade walls of basements & converted crawlspaces finished as follows:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
a) For poured concrete, masonry, & insulated concrete forms, finish with damp-proofing coating.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
b) For wood framed walls, finish with polyethylene and adhesive or other equivalent waterproofing.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.6 Class 1 vapor retarder not installed on interior side of air permeable insulation in ext. below-grade walls. ¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.7 Sump pump covers mechanically attached with full gasket seal or equivalent.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.8 Drain tile installed at the exterior side of footings of basement and crawspace walls, with the top of the drain tile pipe below the bottom of the concrete slab or crawspace floor. Drain tile surrounded with 6 in. of $\frac{1}{2}$ to $\frac{3}{4}$ in. washed or clean gravel and with gravel layer fully wrapped with fabric cloth. Drain tile level or sloped to discharge to outside grade (daylight) or to a sump pump. ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

2. Water-Managed Wall Assembly

2.1 Flashing at bottom of exterior walls with weep holes included for masonry veneer and weep screed for stucco cladding systems, or equivalent drainage system.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.2 Fully sealed continuous drainage plane behind exterior cladding that laps over flashing in Item 2.1 and fully sealed at all penetrations. Additional bond-break drainage plane layer provided behind all stucco and non-structural masonry cladding wall assemblies. ¹¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.3 Window and door openings fully flashed. ¹²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

3. Water-Managed Roof Assembly

3.1 Step and lock-out flashing at all roof-wall intersections, extending 4" on wall surface above roof deck and integrated single-slope with drainage plane above, boot, collar flashing at all roof penetrations. ¹³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.2 For homes that don't have a slab-on-grade foundation and do have expansive or collapsible soils, gutters & downspouts provided that empty to lateral piping that discharges water on sloping final grade 5 ft. from foundation, or to underground catchment system not connected to the foundation drain system that discharges water 10 ft. from foundation. See Footnote for alternatives & exemptions. ¹⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.3 Self-sealing blumastic membrane or equivalent at all valleys & roof deck penetrations. ¹⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.4 In 2009 IECC Climate Zones 5 & higher, self-sealing blumastic membrane or equivalent over sheathing at eaves from the edge of the roof line to > 2 ft. up roof deck from the interior plane of the exterior wall. ¹⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

4. Water-Managed Building Materials

4.1 Walk-to-wall carpet not installed within 2 1/2 ft. of toilets, tubs, and showers.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Cement board or equivalent moisture-resistant backing material installed on all walls behind tub and shower enclosures composed of tile or panel assemblies with caulked joints. Paper-faced backboard shall not be used.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.3 In Warm-Humid climates, Class 1 vapor retarders not installed on the interior side of air permeable insulation in above-grade walls, except at shower and tub walls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.4 Building materials with visible signs of water damage or mold not installed or allowed to remain. ¹⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.5 Framing members & insulation products having high moisture content not enclosed (e.g., with drywall) ¹⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Builder Employee: _____ Date: _____
Builder Signature: _____
Builder has completed Builder Checklist in its entirety, except for items that are checked in the Rater Verified column (if any)?
Rater Signature: _____ Date: _____

We have asked Energy Star for clarification but have not heard back yet.



Water Management Checklist

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
Water Management System Builder Checklist ^{1,2}

Home Address: _____ City: _____ State: _____ Zip Code: _____

1. Water-Managed Site and Foundation

1.1 Paths, stairs, porch slabs, walls, and driveways sloped ≥ 0.25 in. per ft. away from home to edge of surface or 10 ft., whichever is less.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2 Backfill has been tamped and final grade sloped ≥ 0.5 in. per ft. away from home for a 10 ft. See Footnote for alternatives. ⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3 Capillary break beneath all slabs (e.g., slab on grade, basement slab) except crawspace slabs using either a 6 mil polyethylene sheeting, lapped 6-12 in., or a 1 in. extruded polystyrene insulation with taped joints. ⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4 Capillary break at all crawspace floors using a 6 mil polyethylene sheeting, lapped 6-12 in., & installed using one of the following per ^{1,11} :	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.1 Placed beneath a concrete slab, OR	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.2 Lapped up each wall or pier and fastened with furring strips or equivalent, OR	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.3 Secured in the ground at the perimeter using stakes.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5 Exterior surface of below-grade walls of basements & converted crawlspaces finished as follows:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
a) For poured concrete, masonry, & insulated concrete forms, finish with damp-proofing coating.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
b) For wood framed walls, finish with polyethylene and adhesive or other equivalent waterproofing.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.6 Class 1 vapor retarder not installed on interior side of air permeable insulation in ext. below-grade walls. ¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.7 Sump pump covers mechanically attached with full gasket seal or equivalent.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.8 Drain tile installed at the exterior side of footings of basement and crawspace walls, with the top of the drain tile pipe below the bottom of the concrete slab or crawspace floor. Drain tile surrounded with 6 in. of $\frac{1}{2}$ to $\frac{3}{4}$ in. washed or clean gravel and with gravel layer fully wrapped with fabric cloth. Drain tile level or sloped to discharge to outside grade (daylight) or to a sump pump. ⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

2. Water-Managed Wall Assembly

2.1 Flashing at bottom of exterior walls with weep holes included for masonry veneer and weep screed for stucco cladding systems, or equivalent drainage system.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.2 Fully sealed continuous drainage plane behind exterior cladding that laps over flashing in Item 2.1 and fully sealed at all penetrations. Additional bond-break drainage plane layer provided behind all stucco and non-structural masonry cladding wall assemblies. ¹¹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.3 Window and door openings fully flashed. ¹²	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

3. Water-Managed Roof Assembly

3.1 Step and lock-out flashing at all roof-wall intersections, extending 4" on wall surface above roof deck and integrated single-slope with drainage plane above, boot, collar flashing at all roof penetrations. ¹³	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.2 For homes that don't have a slab-on-grade foundation and do have expansive or collapsible soils, gutters & downspouts provided that empty to lateral piping that discharges water on sloping final grade 5 ft. from foundation, or to underground catchment system not connected to the foundation drain system that discharges water 10 ft. from foundation. See Footnote for alternatives & exemptions. ¹⁴	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.3 Self-sealing blumastic membrane or equivalent at all valleys & roof deck penetrations. ¹⁵	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.4 In 2009 IECC Climate Zones 5 & higher, self-sealing blumastic membrane or equivalent over sheathing at eaves from the edge of the roof line to > 2 ft. up roof deck from the interior plane of the exterior wall. ¹⁶	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

4. Water-Managed Building Materials

4.1 Walk-to-wall carpet not installed within 2 1/2 ft. of toilets, tubs, and showers.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2 Cement board or equivalent moisture-resistant backing material installed on all walls behind tub and shower enclosures composed of tile or panel assemblies with caulked joints. Paper-faced backboard shall not be used.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.3 In Warm-Humid climates, Class 1 vapor retarders not installed on the interior side of air permeable insulation in above-grade walls, except at shower and tub walls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.4 Building materials with visible signs of water damage or mold not installed or allowed to remain. ¹⁸	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.5 Framing members & insulation products having high moisture content not enclosed (e.g., with drywall) ¹⁹	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Builder Employee: _____ Date: _____
Builder Signature: _____
Builder has completed Builder Checklist in its entirety, except for items that are checked in the Rater Verified column (if any)?
Rater Signature: _____ Date: _____



Prior allowances to complete certain ES requirements in lieu of IAP requirements, & vice versa, have been deleted and unintentional discrepancies have been aligned. This will ease compliance for homes that earn both labels.



Indoor Air Plus

Now completely a stand alone program



- **Moisture control**
 - **Water Managed site & foundation**
 - Drainage, Capillary break, damp proofed, Etc.
 - **Water managed Wall assemblies**
 - Drainage plane, flashing details
 - **Water managed Roof assemblies**
 - Gutters and flashing
 - **Interior water management**
 - Moisture resistant materials
- **Radon control**
 - Radon resistant features including at least a passive radon system
- **Pest Barriers**
 - Minimize pathway for pests
- **HVAC Systems**
 - **Heating & Cooling equipment**
 - Sizing and design
 - **Ventilation**
 - ASHREA 62.2
 - **Air cleaning and filtration**
 - **Dehumidification**
- **Combustion pollutant control**
 - **Combustion source Controls**
 - Sealed or power vented equipment
 - Attached garages
 - Insolated
- **Low emission materials**
 - Engineered woods, Paints, Carpets
- **Home commissioning**
 - **Duct testing, Pressure balancing, Flows, Etc.**



Water Management Checklist

ENERGY STAR Certified Homes, Version 3 (Rev. 07)
Water Management System Builder Checklist ^{1,2}

Home Address:	City:	State:	Zip Code:	Must Correct:	Builder Verified:	Rater Verified:	N/A:
1. Water-Managed Site and Foundation							
1.1	Patio slabs, porch slabs, walks, and driveways sloped ≥ 0.25 in. per ft. away from home to edge of surface or 10 ft., whichever is less.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.2	Bank fill has been compacted and final grade sloped ≥ 0.5 in. per ft. away from home for ≥ 10 ft. See Footnote for alternatives.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.3	Capillary break beneath all slabs (e.g., slab on grade, basement slab) except crawlspace slabs using either: a 6 mil polyethylene sheeting, tapered 6-12 in., or a 1 in. extruded polystyrene insulation with taped joints.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4	Capillary break at all crawlspace floors using a 6 mil polyethylene sheeting, tapered 6-12 in., & installed using one of the following options:			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.1	Placed beneath a concrete slab, OR			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.2	Lapped up each wall or pier and fastened with furring strips or equivalent, OR			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.4.3	Secured to the ground at the perimeter using stakes.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.5	Exterior surface of below-grade walls of basements & unvented crawlspaces finished as follows: a) For poured concrete, masonry, & insulated concrete forms, finish with damp-proofing coating. b) For wood framed walls, finish with polyethylene and adhesive or other equivalent waterproofing.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.6	Class 1 vapor retarder not installed on interior side of air permeable insulation in ext. below-grade walls.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.7	Sump pump covers mechanically attached with full gasket seal or equivalent.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1.8	Drain tile installed at the exterior side of footings of basement and crawlspace walls, with the top of the drain tile pipe below the bottom of the concrete slab or crawlspace floor. Drain tile surrounded with a 6 in. of 1/2 to 3/4 in. washed or clean gravel and with gravel layer fully wrapped with fabric cloth. Drain tile level or sloped to discharge to outside grade (daylight) or to a sump pump.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. Water-Managed Wall Assembly							
2.1	Flashing at bottom of exterior walls with weep holes included for masonry veneer and weep screed for masonry cladding systems, or equivalent drainage system.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.2	Fully sealed continuous drainage plane behind exterior cladding that laps over flashing in Item 2.1 and fully sealed at all penetrations. Additional bond-break drainage plane layer provided behind all masonry and non-structural masonry cladding wall assemblies.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.3	Window and door openings fully flashed.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3. Water-Managed Roof Assembly							
3.1	Drip and lock-out flashing at all roof-wall intersections, extending a 4" on wall surface above roof deck and integrated single-slope with drainage plane above, boot & collar flashing at all roof penetrations.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.2	For homes that don't have a slab-on-grade foundation and do have expansive or collapsible soils, gutters & downspouts provided that empty to lateral piping that discharges water on sloping final grade a 5 ft. from foundation, or to underground collection system not connected to the foundation drain system that discharges water ≥ 10 ft. from foundation. See Footnote for alternatives & exemptions.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.3	Self-sealing blumastic membrane or equivalent at all valleys & roof deck penetrations.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.4	In 2009 IECC Climate Zones 5 & higher, self-sealing blumastic membrane or equivalent over sheathing & eaves from the edge of the roof line to > 2 ft. up roof deck from the interior plane of the exterior wall.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. Water-Managed Building Materials							
4.1	Wall-to-wall carpet not installed within 2.5 ft. of toilets, tubs, and showers.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.2	Cement board or equivalent moisture-resistant backing material installed on all walls behind tub and shower enclosures composed of tile or panel assemblies with caulked joints. Paper-faced backboard shall not be used.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.3	In Warm-Humid climates, Class 1 vapor retarders not installed on the interior side of air permeable insulation in above-grade walls, except at shower and tub walls.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.4	Building materials with visible signs of water damage or mold not installed or allowed to remain.			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.5	Framing members & insulation products having high moisture content not enclosed (e.g., with drywall).			<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Builder Signature: _____ Date: _____							
Builder has completed Builder Checklist in its entirety, except for items that are checked in the Rater Verified column (if any)?							
Rater Signature: _____ Date: _____							

Difficult items on the checklist:

- Wall-to-wall carpet *not* installed within 2.5 ft. of toilets, tubs, and showers.
- Class 1 vapor retarder not installed on interior side of air permeable insulation in ext. below-grade walls



Energy Star V3 HVAC Checklists

Thank you!

Robby@nrglogic.com

www.nrglogic.com

720-838-0677



Upside down house Szymbark Poland

